

PROJECT : PROPOSED RENOVATION OF STAFF HOUSE AND FRONTAGE DEVELOPMENT
OWNER : INTERNATIONAL PHARMACEUTICAL INCORPORATED
LOCATION : PUROK ROADSIDE, ALIJS, BACOLOD CITY, NEGROS OCCIDENTAL
SUBJECT : BILL OF QUANTITY
DURATION : 150 DAYS

ITEM	DESCRIPTION	SPECIFICATION/ BRAND	QUANTITY	UNIT	UNIT COST			AMOUNT
					MATERIALS	LABOR & EQUIPMENT	TOTAL	
I	GENERAL REQUIREMENTS							₱ 3,687,060.00
1.1	Mobilization and Demobilization	Civil, Structural, Architectural Works and MEPF	1.00	lot		₱ 300,000.00	₱ 300,000.00	₱ 300,000.00
1.2	Temporary Board Up	0.4mm thk. Corrugated GI in 3m high	58.53	lm	₱ 1,200.00	₱ 800.00	₱ 2,000.00	₱ 117,060.00
1.3	Temporary Power & Water Consumption		1.00	lot		₱ 300,000.00	₱ 300,000.00	₱ 300,000.00
1.4	Permits and Clearances	Construction Permit, Building permit, Fencing permit, Occupancy permit, and all necessary permits	1.00	lot		₱ 200,000.00	₱ 200,000.00	₱ 200,000.00
1.5	Site Safety and Health		1.00	lot		₱ 250,000.00	₱ 250,000.00	₱ 250,000.00
1.6	Preparation of As-built, Shop Drawings, Fabrication, Drawings & Submittals		1.00	lot		₱ 150,000.00	₱ 150,000.00	₱ 150,000.00
1.7	Temporary Facilities (Temfacil for material storage)	Material Storage, Site Office and CR	1.00	lot	₱ 350,000.00	₱ 100,000.00	₱ 450,000.00	₱ 450,000.00
1.8	Construction Bonds and Insurances						₱ 0.00	₱ 0.00
	1.8.1 Surety Bond		1.00	lot		₱ 45,000.00	₱ 45,000.00	₱ 45,000.00
	1.8.2 CARI		1.00	lot		₱ 75,000.00	₱ 75,000.00	₱ 75,000.00
	1.8.3 Performance Bond		1.00	lot		₱ 75,000.00	₱ 75,000.00	₱ 75,000.00
	1.8.4 Warranty Bond		1.00	lot		₱ 150,000.00	₱ 150,000.00	₱ 150,000.00
1.9	Periodic Disposal		1.00	lot		₱ 200,000.00	₱ 200,000.00	₱ 200,000.00
1.10	Site Supervision		1.00	lot		₱ 500,000.00	₱ 500,000.00	₱ 500,000.00
1.11	Material Testing	RMC, Rebar, CHB and FDT Test	1.00	lot		₱ 75,000.00	₱ 75,000.00	₱ 75,000.00
1.12	Scaffolding, Forms and Shoring With Complete Accessories		1.00	lot		₱ 300,000.00	₱ 300,000.00	₱ 300,000.00
1.13	Other scopes, miscellaneous, consumables and heavy equipment used to complete the work		1.00	lot		₱ 500,000.00	₱ 500,000.00	₱ 500,000.00
II	PROPOSED RENOVATION OF STAFF HOUSE (Materials, Consumables, Labor & Equipment Cost)							
2.1	Site Works, Civil Works/Structural Works and Metal Works							₱ 2,212,398.05
2.1.1	Demolition Works	Plant Box Interior and Exterior, Concrete Base of perimeter fence, Demolition of concrete Walls, Tiles and grout total area (floor and wall), Stairs and Roof Slab	69.39	cu.m	₱ 0.00	₱ 1,650.00	₱ 1,650.00	₱ 114,497.21
2.1.2	Dismantling Works	Existing- Doors(34sets), Windows(27sets), Water Closets(9units), lavatories(7units), Perimeter Fence (Steel 32m) and other areas necessary	1.00	lot	₱ 0.00	₱ 137,500.00	₱ 137,500.00	₱ 137,500.00
2.1.3	Lay-out and staking		1.00	lot	₱ 0.00	₱ 55,000.00	₱ 55,000.00	₱ 55,000.00
2.1.4	Excavation Works		1.65	cu.m	₱ 0.00	₱ 1,650.00	₱ 1,650.00	₱ 2,724.32
2.1.5	Backfilling Works and Compaction for Excavated Areas		2.32	cu.m	₱ 1,725.00	₱ 880.00	₱ 2,605.00	₱ 6,045.31
2.1.6	Gravel Bedding	3/4"	0.14	cu.m	₱ 2,875.00	₱ 550.00	₱ 3,425.00	₱ 474.88
2.1.7	Reinforcing Steel Bar Works	Inclusion: Footing, Pedestal, Lateral Ties, Stairs, Slab, Lintel Beam and Stiffener Column.			₱ 0.00	₱ 0.00		
2.1.7.1	Grade 40	10mm and 12mm diam.	1,100.71	kg	₱ 53.00	₱ 22.00	₱ 75.00	₱ 82,553.02
2.1.7.2	Grade 60	16mm diam.	430.74	kg	₱ 53.00	₱ 22.00	₱ 75.00	₱ 32,305.86
2.1.8	Formworks	Phenolic Board 3/4"x 4'x 8' (Inclusion: Footing, Pedestal, Stairs, Slab, Lintel Beam and Stiffener Column)	229.79	sq.m	₱ 1,250.00	₱ 750.00	₱ 2,000.00	₱ 459,574.45
2.1.9	Concreting Works	Class A Mixture_3000psi 28days (Inclusion: Footing, Pedestal, Stairs, Slab, Lintel Beam and Stiffener Column).	15.24	cu.m	₱ 6,000.00	₱ 1,550.00	₱ 7,550.00	₱ 115,062.00
2.1.10	Fabrication and Erection of Structural Steel Members with Complete Accessories				₱ 0.00	₱ 0.00	₱ 0.00	₱ 0.00
2.1.10.1	Wide Flange W8x18	6m	1.00	length	₱ 21,700.00	₱ 4,950.00	₱ 26,650.00	₱ 26,650.00
2.1.10.2	Wide Flange W12x45	6m	3.00	length	₱ 28,900.00	₱ 4,950.00	₱ 33,850.00	₱ 101,550.00
2.1.10.3	Wide Flange W12x65	6m	1.00	length	₱ 41,000.00	₱ 4,950.00	₱ 45,950.00	₱ 45,950.00
2.1.10.4	MS Plate 20mm Thk	300mmx400mm	1.00	pc	₱ 1,725.00	₱ 605.00	₱ 2,330.00	₱ 2,330.00
2.1.10.5	MS Plate 25mm Thk	400mmx400mm	8.00	pcs	₱ 2,070.00	₱ 605.00	₱ 2,675.00	₱ 21,400.00
2.1.10.6	Anchor Bolt with Hex Nut and Washer 20mm Ø x 800mm Long		8.00	pcs	₱ 1,618.00	₱ 495.00	₱ 2,113.00	₱ 16,904.00

	2.1.10.7 Mechanical Expansion Bolt with Hex Nut and Washer 12mm Ø	HILTI HST3 Wedge Anchor	15.00	sets	₱ 1,708.00	₱ 495.00	₱ 2,203.00	₱ 33,045.00
	2.1.10.8 Mechanical Expansion Bolt with Hex Nut and Washer 16mm Ø	HILTI HST3 Wedge Anchor	44.00	pcs	₱ 1,725.00	₱ 495.00	₱ 2,220.00	₱ 97,680.00
	2.1.10.9 Square Tube 2"x 2" Sched. 40		3.00	length	₱ 6,915.00	₱ 1,990.00	₱ 8,905.00	₱ 26,715.00
	2.1.10.10 Rectangular Tube 2"x 4"x 6mm thk		1.00	length	₱ 18,492.00	₱ 5,306.00	₱ 23,798.00	₱ 23,798.00
	2.1.10.11 BI Pipe 3" Ø Sched. 40		2.00	length	₱ 1,060.00	₱ 2,025.00	₱ 3,085.00	₱ 6,170.00
	2.1.10.12 Stainless Steel Tube 1-1/2"Ø (Ramp Railings)		4.00	length	₱ 13,765.00	₱ 3,950.00	₱ 17,715.00	₱ 70,860.00
	2.1.10.13 Flat Bar 1-1/2" x 6mm thk		7.00	length	₱ 1,030.00	₱ 295.00	₱ 1,325.00	₱ 9,275.00
	2.1.10.14 Round Bar 12mm Ø	6m	24.47	kg	₱ 435.00	₱ 125.00	₱ 560.00	₱ 13,700.52
	2.1.10.15 Pan Type Steel Deck 0.8mm thk		20.00	sq.m	₱ 1,797.00	₱ 515.00	₱ 2,312.00	₱ 46,240.00
	2.1.10.16 MS Checker Plate 3mm thk	4' x 8'	1.00	sheet	₱ 26,595.00	₱ 7,631.00	₱ 34,226.00	₱ 34,226.00
	2.1.10.17 E6011 Welding Rods 1/8" Ø	Nihonweld	8.00	kg	₱ 180.00	₱ 51.00	₱ 231.00	₱ 1,848.00
	2.1.10.18 E6013 Welding Rods 5/32" Ø	Nihonweld	20.00	kg	₱ 180.00	₱ 52.00	₱ 232.00	₱ 4,640.00
	2.1.10.19 Non-shrink Grout	25 kg	2.00	bags	₱ 230.00	₱ 66.00	₱ 296.00	₱ 592.00
	2.1.11 Septic Tank	4mL x 1.5mW x 2.15mH (3 chambers)	3.00	No.	₱ 0.00	₱ 0.00		
	2.1.11.1 Excavation		43.56	cu.m	₱ 0.00	₱ 1,650.00	₱ 1,650.00	₱ 71,874.00
	2.1.11.2 Gravel Bedding		2.25	cu.m	₱ 2,875.00	₱ 550.00	₱ 3,425.00	₱ 7,706.25
	2.1.11.3 Rebar Works (Grade 40)	10mm and 12mm	1,634.67	kg	₱ 53.00	₱ 22.00	₱ 75.00	₱ 122,600.25
	2.1.11.4 Rebar Works (Grade 60)		235.90	kg	₱ 53.00	₱ 22.00	₱ 75.00	₱ 17,692.50
	2.1.11.5 Formworks		70.13	sq.m	₱ 1,450.00	₱ 770.00	₱ 2,220.00	₱ 155,677.50
	2.1.11.6 Concreting Works	3000 PSI 28days	16.92	cu.m	₱ 6,325.00	₱ 1,650.00	₱ 7,975.00	₱ 134,937.00
	2.1.11.7 6" CHB plastered with complete accessories to complete the works		15.00	sq.m	₱ 1,450.00	₱ 715.00	₱ 2,165.00	₱ 32,475.00
	2.1.11.8 Fittings and Pipe Connection		3.00	unit	₱ 8,625.00	₱ 2,750.00	₱ 11,375.00	₱ 34,125.00
	2.1.12 Consumables		1.00	lot	₱ 17,250.00	₱ 0.00	₱ 17,250.00	₱ 17,250.00
	2.1.13 Other Scopes, Miscellaneous and Consumables used to complete the work		1.00	lot	₱ 28,750.00	₱ 0.00	₱ 28,750.00	₱ 28,750.00
2.2	Architectural Works							₱ 9,576,126.15
	2.2.1 Masonry Works							
	2.2.1.1 6" CHB plastered both sides with complete accessories to complete the works	<i>Inclusion: CHB laying with mortar, plastering and rebar. Exclusion: Stiffener column and lintel Beam.</i>	295.52	sq.m	₱ 1,400.00	₱ 700.00	₱ 2,100.00	₱ 620,592.00
	2.2.1.2 4" CHB plastered both sides with complete accessories to complete the works		214.32	sq.m	₱ 1,300.00	₱ 595.00	₱ 1,895.00	₱ 406,136.40
	2.2.2 Roofing Works				₱ 0.00	₱ 0.00		
	2.2.2.1 Roofing Sheet	0.5mm thk Rib type	403.65	sq.m	₱ 1,750.00	₱ 550.00	₱ 2,300.00	₱ 928,403.23
	2.2.2.2 Roof Insulation Works		403.65	sq.m	₱ 172.00	₱ 77.00	₱ 249.00	₱ 100,509.74
	2.2.2.3 500mm x 1000mm Fiberglass Thermo Plastic Rib Type (Skylight)		30.00	sq.m	₱ 2,277.00	₱ 550.00	₱ 2,827.00	₱ 84,810.00
	2.2.3 Supplied and Installation of Doors and Windows				₱ 0.00	₱ 0.00		
	2.2.3.1 Doors and Hardwares				₱ 0.00	₱ 0.00		
	2.2.3.1.1 D01 Flush Swing Double Glass Door	1.60mWx 2.4mH (12mm Tempered glass w/ 2x2 aluminum frame)	5.00	set/s	₱ 110,400.00	₱ 3,850.00	₱ 114,250.00	₱ 571,250.00
	2.2.3.1.2 D02 Flush Swing Solid Core Door	0.90mWx 2.1mH	2.00	set/s	₱ 5,175.00	₱ 3,850.00	₱ 9,025.00	₱ 18,050.00
	2.2.3.1.3 D03 Flush Swing Solid Core Door	0.80mWx 2.1mH	8.00	set/s	₱ 5,175.00	₱ 3,850.00	₱ 9,025.00	₱ 72,200.00
	2.2.3.1.4 D04 Flush Swing Door (PVC Toilet Door)	0.60mWx 2.1mH	16.00	set/s	₱ 4,025.00	₱ 3,850.00	₱ 7,875.00	₱ 126,000.00
	2.2.3.1.5 D05 Flush Swing Door (PVC Toilet Door)	0.80mWx 2.1mH	3.00	set/s	₱ 4,025.00	₱ 3,850.00	₱ 7,875.00	₱ 23,625.00
	2.2.3.1.6 D06 Flush Swing Panic Door (Solid Wooden Door)	0.90mWx 2.1mH	1.00	set/s	₱ 14,375.00	₱ 3,850.00	₱ 18,225.00	₱ 18,225.00
	2.2.3.1.7 Roll up Door	5.00m W x 2.20m H	5.00	set/s	₱ 63,250.00	₱ 8,250.00	₱ 71,500.00	₱ 357,500.00
	2.2.3.2 Windows and Hardwares				₱ 0.00	₱ 0.00	₱ 0.00	₱ 0.00
	2.2.3.2.1 W01 Fixed Window	1.575mWx1.85mH (10mm thk tempered glass, 2x6 aluminum frame)	4.00	set/s	₱ 28,934.00	₱ 2,750.00	₱ 31,684.00	₱ 126,736.00
	2.2.3.2.2 W02 Frameless Fixed Window	1.50mWx 2.85mH (10mm thk tempered glass, 2x6 aluminum frame)	4.00	set/s	₱ 41,788.00	₱ 2,750.00	₱ 44,538.00	₱ 178,152.00
	2.2.3.2.3 W03 Frameless Fixed Window	2.40mWx 1.85mH (10mm thk tempered glass, 2x6 aluminum frame)	1.00	set/s	₱ 43,400.00	₱ 2,750.00	₱ 46,150.00	₱ 46,150.00
	2.2.3.2.4 W04 Frameless Fixed Window	1.20mWx 1.85mH (10mm thk tempered glass, 2x6 aluminum frame)	1.00	set/s	₱ 21,700.00	₱ 2,750.00	₱ 24,450.00	₱ 24,450.00
	2.2.3.2.5 W05 Awning Window	0.60mWx 0.65mH (1 1/2 thk, 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide divider)	7.00	set/s	₱ 4,710.00	₱ 2,750.00	₱ 7,460.00	₱ 52,220.00
	2.2.3.2.6 W06 Sliding Window	2.25mWx0.5mH (1 1/2 thk, 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide divider)	5.00	set/s	₱ 10,752.00	₱ 2,750.00	₱ 13,502.00	₱ 67,510.00
	2.2.3.2.7 W07 Sliding Window with Awning Window	3.10mWx1.5mH (1 1/2 thk, 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide divider)	1.00	set/s	₱ 63,395.00	₱ 2,750.00	₱ 66,145.00	₱ 66,145.00
	2.2.3.2.8 W08 Sliding Window	1.80m x 1.250m (1 1/2 thk, 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide divider)	1.00	set/s	₱ 21,995.00	₱ 2,750.00	₱ 24,745.00	₱ 24,745.00
	2.2.3.2.9 W09 Awning Window	0.70m x 1.25m (1 1/2 thk, 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide aluminum frame)	7.00	set/s	₱ 10,565.00	₱ 2,750.00	₱ 13,315.00	₱ 93,205.00
	2.2.3.2.10 W10 Jalousie Window	1.20m x 1.25m (13 blades thk light grey tempered glass, 100mm thk, 50mm wide divider)	2.00	set/s	₱ 14,662.00	₱ 2,750.00	₱ 17,412.00	₱ 34,824.00
	2.2.3.2.11 W11 Sliding Window	2.4m x 1.25m (1 1/2 thk, 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide divider)	3.00	set/s	₱ 29,325.00	₱ 2,750.00	₱ 32,075.00	₱ 96,225.00
	2.2.3.2.12 W12 Sliding Window	0.9m x 2.350m (2 x 6 Aluminum frame, powder coated black w/ 10mm thk	1.00	set/s	₱ 20,675.00	₱ 2,750.00	₱ 23,425.00	₱ 23,425.00

	2.2.3.2.13 W13 Sliding Window	0.70m x 0.901m (1 1/2 thk , 50mm wide aluminum divider, 10mm thk light grey tempered glass, 100mm thk, 50mm wide aluminum framing)	2.00	set/s	₱ 6,160.00	₱ 2,750.00	₱ 8,910.00	₱ 17,820.00
	2.2.4 Ceiling Work With Complete Framing System (GF-2F)	Board with complete framing system with accessories	701.00	sq.m	₱ 1,200.00	₱ 600.00	₱ 1,800.00	₱ 1,261,800.00
	2.2.5 Floor Finishes (GF and 2F)	Tiles Work (Inclusion: Tiles, Tile grout, Tile Adhesive, Cement and Fined Sand)			₱ 0.00	₱ 0.00		
	2.2.5.1 FF01 (60 x 60 Porcelain Grey Tiles)		613.27	sq.m	₱ 1,200.00	₱ 600.00	₱ 1,800.00	₱ 1,103,889.60
	2.2.5.2 FF03 (30 x 60 Non-Skid Porcelain Tiles, Walnut Color)		71.82	sq.m	₱ 1,200.00	₱ 600.00	₱ 1,800.00	₱ 129,274.20
	2.2.5.3 FF04 (40 x 40 Non-Skid Outdoor Porcelain Grey Tiles)		17.53	sq.m	₱ 1,200.00	₱ 600.00	₱ 1,800.00	₱ 31,561.20
	2.2.6 Wall Finishes (GF and 2F)				₱ 0.00	₱ 0.00	₱ 0.00	₱ 0.00
	2.2.6.1 WF01 (White Semi-Gloss Plant Finish	1 coat (Concrete Primer and Sealer), 2coats (Top Coat finish)	604.92	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 477,886.80
	2.2.6.2 WF02 (Light Grey Semi-Gloss Paint Finish	1 coat (Concrete Primer and Sealer), 2coats (Top Coat finish)	144.67	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 114,289.14
	2.2.6.3 WF04 (Exterior WPC Fluted Panel Color Beige-Toilet Partition)		3.74	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 2,954.60
	2.2.6.4 WF06 (60 x 60 Light Beige Porcelain Tiles)		132.60	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 104,751.35
	2.2.6.5 WF07 (Stainless Steel Tile Trim)		56.40	ln.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 44,553.63
	2.2.6.6 WF09 (2" Thk. Black Granite Slab)	1coat (Concrete Primer and Sealer), 2coats (Top Coat finish)	40.49	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 31,987.02
	2.2.7 Paint Finish on Ceiling	CF01 (White Ivory Satin) (Primer Sealer 1coat,	765.41	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 604,673.57
	2.2.8 Waterproofing Include Complete Accessories For Wet Areas				₱ 0.00	₱ 0.00		
	2.2.8.1 Ground Floor (CR)	ous and Reactive Waterproofing	33.11	sq.m	₱ 920.00	₱ 330.00	₱ 1,250.00	₱ 41,387.50
	2.2.8.2 Second Floor (CR)	embrane Waterproofing (2 Coat	38.71	sq.m	₱ 2,300.00	₱ 935.00	₱ 3,235.00	₱ 125,223.62
	2.2.8.3 Septic Tank	Cementitious Waterproofing (2 coats)	160.22	sq.m	₱ 920.00	₱ 330.00	₱ 1,250.00	₱ 200,268.75
	2.2.9 Staircase Includes Stair railings, steps with complete connectors and accessories necessary to complete the works				₱ 0.00	₱ 0.00		
	2.2.9.1 Rectangular Tube Handrail (2 x 3 x 0.3mm Thk.)	Painted Black	2.00	lengths	₱ 3,453.00	₱ 990.00	₱ 4,443.00	₱ 8,886.00
	2.2.9.2 Rectangular Tube (2 x 2 x 0.3mm Thk.)	Painted Black	3.00	lengths	₱ 3,180.00	₱ 912.00	₱ 4,092.00	₱ 12,276.00
	2.2.9.3 Stainless Steel Stair Nosing	6m	5.00	lengths	₱ 647.00	₱ 185.00	₱ 832.00	₱ 4,160.00
	2.2.10 Steel Member	Primer, Matte Black Paint and Paint Thinner (2 Coats)	63.40	sq.m	₱ 6,322.00	₱ 330.00	₱ 6,652.00	₱ 421,736.80
	2.2.11 Kitchen Counters and cabinetries, bedroom wardrobes with required hardwares and accessories and other related Scope to complete the works				₱ 0.00	₱ 0.00		
	2.2.11.1 Bedroom Cabinet	1.40m W x 2.4m H	10.00	sets	₱ 21,735.00	₱ 6,237.00	₱ 27,972.00	₱ 279,720.00
	2.2.11.2 Kitchen Cabinet	2.95m x 1.15m	4.00	sets	₱ 21,945.00	₱ 6,297.00	₱ 28,242.00	₱ 112,968.00
	2.2.11.3 TV Console with complete accessories	2.05m W x 2.7m H	1.00	sets	₱ 35,805.00	₱ 10,275.00	₱ 46,080.00	₱ 46,080.00
	2.2.11.3.1 Rectangular Tube (2 x 2 x 0.3mm Thk.)	(Pre-painted Beige)	5.00	lengths	₱ 3,452.00	₱ 990.00	₱ 4,442.00	₱ 22,210.00
	2.2.11.4 Toilet Partition				₱ 0.00	₱ 0.00	₱ 0.00	₱ 0.00
	2.2.11.4.1 1.8m High Toilet Partition in Satin Walnut Paint Finish (With Complete Accessories)	0.8m W x 1.8m H (Pre-painted)	5.00	sets	₱ 9,315.00	₱ 2,673.00	₱ 11,988.00	₱ 59,940.00
	2.2.11.4.2 2m High Urinal Partition in Satin Walnut Paint Finish (With Complete Accessories)	0.55m W x 1.20m H (Pre-painted)	2.00	sets	₱ 4,270.00	₱ 1,225.00	₱ 5,495.00	₱ 10,990.00
	2.2.12.5 Kitchen Countertop				₱ 0.00	₱ 0.00		
	2.2.12.5.1 Common Kitchen (White Granite Slab Countertop)	h L x 0.6m W x 0.85m H x 0.05m	1.00	unit	₱ 14,375.00	₱ 0.00	₱ 14,375.00	₱ 14,375.00
	2.2.12.5.2 Branch Manager Kitchen (White Granite Slab Countertop)	h L x 0.6m W x 0.85m H x 0.05m	1.00	unit	₱ 14,375.00	₱ 0.00	₱ 14,375.00	₱ 14,375.00
	2.2.12 Consumables		1.00	lot	₱ 57,500.00	₱ 0.00	₱ 57,500.00	₱ 57,500.00
	2.2.13 Other scopes, miscellaneous and consumables used to complete the work		1.00	lot	₱ 57,500.00	₱ 0.00	₱ 57,500.00	₱ 57,500.00
	2.3 Electrical Works							₱ 3,933,705.50
	<i>Power and Lighting System</i>	<i>Installation of Power and Lighting devices, including fittings, supply and installation of hangers, supports other</i>						
	2.3.1 WIRES AND CABLES							
	2.3.1.1 3.5mm ² THHN/THWN	PHELPSDODGE	1,420.00	mts	₱ 55.00	₱ 16.50	₱ 71.50	₱ 101,530.00
	2.3.1.2 5.5mm ² THHN/THWN	PHELPSDODGE	2,400.00	mts	₱ 75.00	₱ 22.50	₱ 97.50	₱ 234,000.00
	2.3.1.3 3.5mm ² THHN/THWN8.0mm ² THHN/THWN	PHELPSDODGE	100.00	mts	₱ 110.00	₱ 33.00	₱ 143.00	₱ 14,300.00
	2.3.1.4 14.0mm ² THHN/THWN	PHELPSDODGE	500.00	mts	₱ 185.00	₱ 55.50	₱ 240.50	₱ 120,250.00
	2.3.1.5 30.0mm ² THHN/THWN	PHELPSDODGE	220.00	mts	₱ 380.00	₱ 114.00	₱ 494.00	₱ 108,680.00
	2.3.1.6 50.0mm ² THHN/THWN	PHELPSDODGE	100.00	mts	₱ 650.00	₱ 195.00	₱ 845.00	₱ 84,500.00
	2.3.1.7 2.0mm ² TW (Grounding)	PHELPSDODGE	1,900.00	mts	₱ 30.00	₱ 9.00	₱ 39.00	₱ 74,100.00
	2.3.1.8 5.5mm ² TW (Grounding)	PHELPSDODGE	200.00	mts	₱ 75.00	₱ 22.50	₱ 97.50	₱ 19,500.00
	2.3.1.9 8.0mm ² TW (Grounding)	PHELPSDODGE	100.00	mts	₱ 110.00	₱ 33.00	₱ 143.00	₱ 14,300.00
	2.3.1.10 14.0mm ² TW (Grounding)	PHELPSDODGE	120.00	mts	₱ 185.00	₱ 55.50	₱ 240.50	₱ 28,860.00
	<i>Roughing-ins and Fittings</i>		1.00	lot	₱ 0.00	₱ 25,000.00	₱ 25,000.00	₱ 25,000.00
	<i>Installation of uPVC Pipe, including fittings, supply and installation of hangers, supports, marking, paintings and other miscellaneous items as required to complete the system</i>				₱ 0.00			
	2.3.2 PVC PIPE				₱ 0.00			
	2.3.2.1 20mm dia PVC Pipe	EMERALD	203.00	lghts	₱ 155.00	₱ 46.50	₱ 201.50	₱ 40,904.50
	2.3.2.2 20mm dia adapter with locknut	EMERALD	102.00	pcs	₱ 45.00	₱ 13.50	₱ 58.50	₱ 5,967.00
	2.3.2.3 20mm dia flexible conduit	MCGILL	50.00	mts	₱ 260.00	₱ 78.00	₱ 338.00	₱ 16,900.00
	2.3.2.4 20mm dia flexible conduit connector	MCGILL	25.00	pcs	₱ 130.00	₱ 39.00	₱ 169.00	₱ 4,225.00
	2.3.2.5 20mm dia EMT Pipe	PANASONIC	30.00	lghts	₱ 530.00	₱ 159.00	₱ 689.00	₱ 20,670.00
	2.3.2.6 20mm dia adapter with locknut	PANASONIC	15.00	pcs	₱ 45.00	₱ 13.50	₱ 58.50	₱ 877.50
	2.3.2.7 25mm dia PVC Pipe	EMERALD	450.00	lghts	₱ 235.00	₱ 70.50	₱ 305.50	₱ 137,475.00
	2.3.2.8 25mm dia adapter with locknut	EMERALD	225.00	pcs	₱ 55.00	₱ 16.50	₱ 71.50	₱ 16,087.50
	2.3.2.9 32mm dia PVC Pipe	EMERALD	10.00	lghts	₱ 310.00	₱ 93.00	₱ 403.00	₱ 4,030.00
	2.3.2.10 32mm dia adapter with locknut	EMERALD	5.00	pcs	₱ 65.00	₱ 19.50	₱ 84.50	₱ 422.50

	2.3.2.11 40mm dia PVC Pipe	EMERALD	67.00	lights	₱ 390.00	₱ 117.00	₱ 507.00	₱ 33,969.00
	2.3.2.12 40mm diameter adapter with locknut	EMERALD	10.00	pcs	₱ 80.00	₱ 24.00	₱ 104.00	₱ 1,040.00
	2.3.2.13 50mm dia PVC Pipe	EMERALD	40.00	lights	₱ 495.00	₱ 148.50	₱ 643.50	₱ 25,740.00
	2.3.2.14 50mm diameter adapter with locknut	EMERALD	10.00	pcs	₱ 110.00	₱ 33.00	₱ 143.00	₱ 1,430.00
	2.3.2.15 80mm diameter adapter with locknut	EMERALD	10.00	pcs	₱ 180.00	₱ 54.00	₱ 234.00	₱ 2,340.00
	2.3.3 BOXES AND PULLBOXES				₱ 0.00			
	2.3.3.1 Junction box with cover 4"x4"	EMERALD	200.00	pcs	₱ 65.00	₱ 19.50	₱ 84.50	₱ 16,900.00
	2.3.3.2 Utility box 2"x4"	EMERALD	130.00	pcs	₱ 55.00	₱ 16.50	₱ 71.50	₱ 9,295.00
	2.3.3.3 Square box with cover 8"x8"x6"	EMERALD	30.00	pcs	₱ 85.00	₱ 25.50	₱ 110.50	₱ 3,315.00
	2.3.3.4 GI Wire #16		10.00	kg	₱ 180.00	₱ 54.00	₱ 234.00	₱ 2,340.00
	2.3.3.5 PVC Solvent, 400cc	EMERALD	8.00	liters	₱ 290.00	₱ 87.00	₱ 377.00	₱ 3,016.00
	2.3.4 WIRING DEVICES AND ACCESSORIES				₱ 0.00			
	2.3.4.1 Convenience outlet duplex type with ground	PANASONIC	50.00	pcs	₱ 760.00	₱ 228.00	₱ 988.00	₱ 49,400.00
	2.3.4.2 Floor-mounted Duplex Outlet	PANASONIC	2.00	pcs	₱ 7,700.00	₱ 2,310.00	₱ 10,010.00	₱ 20,020.00
	2.3.4.3 1-Gang switch in wide series plate	PANASONIC	27.00	pcs	₱ 215.00	₱ 64.50	₱ 279.50	₱ 7,546.50
	2.3.4.4 2-Gang switch in wide series plate	PANASONIC	15.00	pcs	₱ 360.00	₱ 108.00	₱ 468.00	₱ 7,020.00
	2.3.4.5 3-Gang switch in wide series plate	PANASONIC	20.00	pcs	₱ 465.00	₱ 139.50	₱ 604.50	₱ 12,090.00
	2.3.4.6 1-Gang 3-Way switch	PANASONIC	5.00	pcs	₱ 275.00	₱ 82.50	₱ 357.50	₱ 1,787.50
	2.3.4.7 GFCI outlet duplex type with ground	PANASONIC	27.00	pcs	₱ 1,035.00	₱ 310.50	₱ 1,345.50	₱ 36,328.50
	2.3.5 LIGHTING FIXTURES AND ACCESSORIES				₱ 0.00			
	2.3.5.1 LED Recessed Circular Downlight, 18W	OMNI	75.00	pcs	₱ 1,000.00	₱ 300.00	₱ 1,300.00	₱ 97,500.00
	2.3.5.2 LED Recessed Circular Downlight, 6W	OMNI	120.00	pcs	₱ 720.00	₱ 216.00	₱ 936.00	₱ 112,320.00
	2.3.5.3 Emergency lights	OMNI	20.00	pcs	₱ 4,025.00	₱ 1,207.50	₱ 5,232.50	₱ 104,650.00
	2.3.6 PANEL BOARDS AND CIRCUITS				₱ 0.00			
	Assembly in NEMA-1 enclosure powder coated complete with crimped type terminal lugs and grounding busbar (Wall mounted)				₱ 0.00			
	2.3.6.1 MDP/MTS with 6 branches (MDP-1)		1.00	assy	₱ 201,250.00	₱ 60,375.00	₱ 261,625.00	₱ 261,625.00
	2.3.6.2 80AT, 3-Pole, 100AF, 30KAIC, MCCB (Main Breaker)	SCHNEIDER	1.00	pc	₱ 21,000.00	₱ 6,300.00	₱ 27,300.00	₱ 27,300.00
	2.3.6.3 60AT, 3-Pole, 100AF, 30KAIC, MCB	SCHNEIDER (Branches)	6.00	pcs	₱ 15,100.00	₱ 4,530.00	₱ 19,630.00	₱ 117,780.00
	2.3.6.4 MDP/MTS with 6 branches (MDP-2)		1.00	assy	₱ 201,250.00	₱ 60,375.00	₱ 261,625.00	₱ 261,625.00
	2.3.6.5 100AT, 3-Pole, 100AF, 30KAIC, MCCB (Main Breaker)	SCHNEIDER	1.00	pc	₱ 24,300.00	₱ 7,290.00	₱ 31,590.00	₱ 31,590.00
	2.3.6.6 40AT, 3-Pole, 100AF, 30KAIC, MCB	SCHNEIDER (Branches)	1.00	pcs	₱ 24,300.00	₱ 7,290.00	₱ 31,590.00	₱ 31,590.00
	2.3.6.7 60AT, 3-Pole, 100AF, 30KAIC, MCB	SCHNEIDER (Branches)	3.00	pcs	₱ 3,010.00	₱ 903.00	₱ 3,913.00	₱ 11,739.00
	2.3.6.8 100AT, 3-Pole, 100AF, 30KAIC, MCB	SCHNEIDER (Branches)	2.00	pcs	₱ 8,840.00	₱ 2,652.00	₱ 11,492.00	₱ 22,984.00
	2.3.6.9 Branch Panel Board (Lease rooms) with 6 branches							
	Main Breaker							
	60AT, 3-Pole, 100AF, 30KAIC, MCB	Main Breaker (SCHNEIDER)	5.00	assy	51,030.00	15,309.00	66,339.00	331,695.00
	Branches:							
	16AT, 2-Pole, 100AF, 10KAIC, MCB	Branches (SCHNEIDER)						
	20AT, 2-Pole, 100AF, 10KAIC, MCB	Branches (SCHNEIDER)						
	32AT, 2-Pole, 100AF, 10KAIC, MCB	Branches (SCHNEIDER)						
	2.3.6.10 Branch Panel Board (Lighting - 2nd floor) with 6 branches		1.00	assy	₱ 15,095.00	₱ 4,528.50	₱ 19,623.50	₱ 19,623.50
	40AT, 3-Pole, 100AF, 30KAIC, MCB	Main Breaker (SCHNEIDER)	1.00	pc.	₱ 12,220.00	₱ 3,666.00	₱ 15,886.00	₱ 15,886.00
	16AT, 2-Pole, 100AF, 10KAIC, MCB	Branches (SCHNEIDER)	6.00	pcs	₱ 5,030.00	₱ 1,509.00	₱ 6,539.00	₱ 39,234.00
	2.3.6.11 Branch Panel Board (Outlet - 2nd floor) with 8 branches		1.00	assy	₱ 15,100.00	₱ 4,530.00	₱ 19,630.00	₱ 19,630.00
	80AT, 3-Pole, 100AF, 30KAIC, MCCB	Main Breaker (SCHNEIDER)	1.00	pc	₱ 20,845.00	₱ 6,253.50	₱ 27,098.50	₱ 27,098.50
	32AT, 2-Pole, 100AF, 10KAIC, MCB	Branches (SCHNEIDER)	10.00	pcs	₱ 10,350.00	₱ 3,105.00	₱ 13,455.00	₱ 134,550.00
	2.3.6.12 Branch Panel Board (ACU - 2nd floor) with 10 branches		1.00	assy	₱ 44,275.00	₱ 13,282.50	₱ 57,557.50	₱ 57,557.50
	100AT, 3-Pole, 100AF, 30KAIC, MCB	Main Breaker (SCHNEIDER)	1.00	pc	₱ 24,300.00	₱ 7,290.00	₱ 31,590.00	₱ 31,590.00
	32AT, 2-Pole, 100AF, 10KAIC, MCB	Branches (SCHNEIDER)	10.00	pcs	₱ 10,350.00	₱ 3,105.00	₱ 13,455.00	₱ 134,550.00
	2.3.6.13 ECB Nema 3R Metal Enclosure		15.00	assy	₱ 6,830.00	₱ 2,049.00	₱ 8,879.00	₱ 133,185.00
	2.3.6.14 32AT, 2-Pole, 100AF, 10KAIC, MCCB	SCHNEIDER	15.00	pcs	₱ 7,910.00	₱ 2,373.00	₱ 10,283.00	₱ 154,245.00
	2.3.6.15 150AT, 3-Pole, 150AF, 36KAIC, MCB	Circuit Breaker (SCHNEIDER)	1.00	pcs	₱ 21,155.00	₱ 6,346.50	₱ 27,501.50	₱ 27,501.50
	2.3.6.16 Electric Submeter	With Base (ACLARA CL200)	5.00	pcs	₱ 47,000.00	₱ 14,100.00	₱ 61,100.00	₱ 305,500.00
	Testing and Commissioning		1.00	lot	₱ 57,500.00		₱ 57,500.00	₱ 57,500.00
	2.7.7 Miscellaneous and Consumables		1.00	lot	₱ 28,750.00		₱ 28,750.00	₱ 28,750.00
	2.3.8 Other scopes, miscellaneous and consumables used to complete the work		1.00	lot	₱ 28,750.00		₱ 28,750.00	₱ 28,750.00
2.4	Mechanical Works							₱ 2,550,334.00
	<i>Installation of Toilet Exhaust Ducts, including fittings, supply and installation of hangers, supports, marking, paintings and other miscellaneous items as required to complete the system</i>							
	2.4.1 Air Conditioning Units	PANASONIC						
	2.4.1.1 ACCU/FCU, Wall Mounted Split Type	2.0HP	15.00	unit/s	₱ 71,875.00	₱ 14,375.00	₱ 86,250.00	₱ 1,293,750.00
	2.4.1.2 Aircon Water Drain Pipe	3/4" dia, 3m per length	80.00	lngh/s	₱ 155.00	₱ 31.00	₱ 186.00	₱ 14,880.00
	2.4.1.3 Closed Cell Rubber Insulation	19mm thk, 2m per length	120.00	mts	₱ 140.00	₱ 28.00	₱ 168.00	₱ 20,160.00
	2.4.1.4 Polyethylene Finishing Tape (AeroTape)	3meters/roll	90.00	unit/s	₱ 655.00	₱ 131.00	₱ 786.00	₱ 70,740.00
	2.4.1.5 Copper Tube, 1/4 inch		240.00	mts	₱ 190.00	₱ 38.00	₱ 228.00	₱ 54,720.00
	2.4.1.6 Copper Tube, 1/2 inch		240.00	mts	₱ 215.00	₱ 43.00	₱ 258.00	₱ 61,920.00
	2.4.1.7 Mapp Gas	14.1 oz	13.00	unit/s	₱ 405.00	₱ 81.00	₱ 486.00	₱ 6,318.00
	2.4.1.8 Copper Torch		4.00	unit/s	₱ 3,000.00	₱ 600.00	₱ 3,600.00	₱ 14,400.00
	2.4.1.9 Silver Rod	20 pcs/pack	1.00	unit/s	₱ 360.00	₱ 72.00	₱ 432.00	₱ 432.00
	2.4.1.10 Brackets		15.00	unit/s	₱ 400.00	₱ 80.00	₱ 480.00	₱ 7,200.00
	2.4.1.11 Supports and Hangers		1.00	lot	₱ 8,625.00	₱ 1,725.00	₱ 10,350.00	₱ 10,350.00
	2.4.2 Toilet Exhaust Fans	FIREFLY			₱ 0.00			
	2.4.2.1 Exhaust Fans	Ceiling Mounted, 25W	20.00	unit/s	₱ 2,155.00	₱ 431.00	₱ 2,586.00	₱ 51,720.00
	2.4.2.2 Vent End Cap	4" dia	20.00	unit/s	₱ 645.00	₱ 129.00	₱ 774.00	₱ 15,480.00
	2.4.2.3 PVC Pipe	4" dia	140.00	lngh/s	₱ 1,325.00	₱ 265.00	₱ 1,590.00	₱ 222,600.00
	2.4.2.4 Flexible Duct	4" dia	90.00	mts	₱ 790.00	₱ 158.00	₱ 948.00	₱ 85,320.00
	2.4.2.5 Aluminun Duct Tape	4" dia	10.00	unit/s	₱ 505.00	₱ 101.00	₱ 606.00	₱ 6,060.00
	2.4.2.6 Supports and Hangers		1.00	lot	₱ 17,250.00	₱ 3,450.00	₱ 20,700.00	₱ 20,700.00
	2.4.3 Ceiling Fans	PANASONIC			₱ 0.00			
	2.4.3.1 Ceiling Fan	Ceiling Mounted, 25W	3.00	unit/s	₱ 20,845.00	₱ 4,169.00	₱ 25,014.00	₱ 75,042.00
	2.4.3.2 Supports and Hangers		1.00	lot	₱ 17,250.00	₱ 3,450.00	₱ 20,700.00	₱ 20,700.00
	2.4.4 Rangehoods	MIDEA			₱ 0.00			
	2.4.4.1 Rangehood	FP-65NRH060MRTL	2.00	unit/s	₱ 6,615.00	₱ 1,323.00	₱ 7,938.00	₱ 15,876.00
	2.4.4.2 Vent End Cap	6" dia	3.00	unit/s	₱ 935.00	₱ 187.00	₱ 1,122.00	₱ 3,366.00
	2.4.4.3 PVC Pipe	6" dia	10.00	lngh/s	₱ 2,485.00	₱ 497.00	₱ 2,982.00	₱ 29,820.00
	2.4.4.4 PVC Elbow	90 deg, 6" dia	5.00	unit/s	₱ 1,005.00	₱ 201.00	₱ 1,206.00	₱ 6,030.00
	2.4.4.5 Supports and Hangers		1.00	lot	₱ 17,250.00	₱ 3,450.00	₱ 20,700.00	₱ 20,700.00

	2.4.5 Fire Protection				₱ 0.00			
	2.4.5.1 Fire Extinguisher	HFC-236FA (10 lbs)	15.00	unit/s	₱ 14,375.00	₱ 2,875.00	₱ 17,250.00	₱ 258,750.00
	2.4.6 Others				₱ 0.00			
	2.4.6.1 Consumables		1.00	lot	₱ 17,250.00	₱ 3,450.00	₱ 20,700.00	₱ 20,700.00
	2.4.6.2 Fittings, equipment and accessories not stated above but required to finish the work		1.00	lot	₱ 23,000.00	₱ 4,600.00	₱ 27,600.00	₱ 27,600.00
	2.4.7 Contingencies		1.00	lot	₱ 28,750.00		₱ 28,750.00	₱ 28,750.00
	2.4.8 Testing and Commissioning		1.00	lot	₱ 57,500.00		₱ 57,500.00	₱ 57,500.00
	2.4.9 Other scopes, miscellaneous and consumables used to complete the work		1.00	lot	₱ 28,750.00		₱ 28,750.00	₱ 28,750.00
	2.5 Plumbing Works							₱ 2,680,938.00
	2.5.1 Waterline	Installation of Polypropylene Random Copolymer (PPRC) pipes PN20, including fittings, supply and installation of hangers, supports, marking, paintings and other						
	2.5.1.1 PPR Pipe	Fujipipes 1-1/4"(40mmØ)	16.00	length/s	₱ 2,230.00	₱ 446.00	₱ 2,676.00	₱ 42,816.00
		Fujipipes 1"(32mmØ)	58.00	length/s	₱ 1,345.00	₱ 269.00	₱ 1,614.00	₱ 93,612.00
		Fujipipes 3/4"(25mmØ)	54.00	length/s	₱ 805.00	₱ 161.00	₱ 966.00	₱ 52,164.00
		Fujipipes 1/2"(20mmØ)	2.00	length/s	₱ 565.00	₱ 113.00	₱ 678.00	₱ 1,356.00
	2.5.1.2 PPR Elbow 90deg	Fujipipes 1-1/4" (40mmØ)	11.00	pc/s	₱ 160.00	₱ 32.00	₱ 192.00	₱ 2,112.00
		Fujipipes 1" (32mmØ)	110.00	pc/s	₱ 150.00	₱ 30.00	₱ 180.00	₱ 19,800.00
		Fujipipes 3/4"(25mmØ)	16.00	pc/s	₱ 80.00	₱ 16.00	₱ 96.00	₱ 1,536.00
	2.5.1.3 PPR Tee Equal	Fujipipes 1-1/4" (40mmØ)	2.00	pc/s	₱ 195.00	₱ 39.00	₱ 234.00	₱ 468.00
		Fujipipes 1" (32mmØ)	23.00	pc/s	₱ 115.00	₱ 23.00	₱ 138.00	₱ 3,174.00
	2.5.1.4 PPR Tee Reducer	Fujipipes 1-1/4" (40mmØ) x 1" (32mmØ)	13.00	pc/s	₱ 400.00	₱ 80.00	₱ 480.00	₱ 6,240.00
		Fujipipes 1" (40mmØ) x 3/4"(25mmØ)	4.00	pc/s	₱ 245.00	₱ 49.00	₱ 294.00	₱ 1,176.00
		Fujipipes 1" (32mmØ) x 3/4" (25mmØ)	45.00	pc/s	₱ 215.00	₱ 43.00	₱ 258.00	₱ 11,610.00
	2.5.1.5 PPR Coupling Reducer	Fujipipes 1 1/4" (40mmØ) x 1" (32mmØ)	6.00	pc/s	₱ 145.00	₱ 29.00	₱ 174.00	₱ 1,044.00
		Fujipipes 1" (32mmØ) x 3/4"(25mmØ)	69.00	pc/s	₱ 130.00	₱ 26.00	₱ 156.00	₱ 10,764.00
		Fujipipes 3/4"(25mmØ) x 1/2"(20mmØ)	56.00	pc/s	₱ 110.00	₱ 22.00	₱ 132.00	₱ 7,392.00
	2.5.1.6 PPR Female Threaded Tee	Fujipipes 20mm x 1/2"Ø	75.00	pc/s	₱ 450.00	₱ 90.00	₱ 540.00	₱ 40,500.00
	2.5.1.7 PPR Female Threaded Elbow	Fujipipes 32mmØ x 1"Ø	5.00	pc/s	₱ 360.00	₱ 72.00	₱ 432.00	₱ 2,160.00
		Fujipipes 20mm x 1/2"Ø	3.00	pc/s	₱ 220.00	₱ 44.00	₱ 264.00	₱ 792.00
	2.5.1.8 PPR End Cap	Fujipipes 1"(32mmØ)	29.00	pc/s	₱ 70.00	₱ 14.00	₱ 84.00	₱ 2,436.00
		Fujipipes 3/4"(25mmØ)	58.00	pc/s	₱ 60.00	₱ 12.00	₱ 72.00	₱ 4,176.00
	2.5.1.9 Brass Gate Valve 32mmØ	Kitz 1" (32mmØ)	5.00	pc/s	₱ 7,980.00	₱ 1,596.00	₱ 9,576.00	₱ 47,880.00
	2.5.1.10 G.I. PIPE	Seamless 1-1/4" (40mmØ)	1.00	length/s	₱ 3,205.00	₱ 641.00	₱ 3,846.00	₱ 3,846.00
		Seamless 1" (32mmØ)	1.00	length/s	₱ 2,415.00	₱ 483.00	₱ 2,898.00	₱ 2,898.00
	2.5.1.11 G.I. Tee Equal 1" 32mmØ	Mech	4.00	pc/s	₱ 375.00	₱ 75.00	₱ 450.00	₱ 1,800.00
	2.5.1.12 G.I. Tee Elbow 90deg 1" 32mmØ	Mech	10.00	pc/s	₱ 150.00	₱ 30.00	₱ 180.00	₱ 1,800.00
	2.5.1.13 G.I. Threaded Union 1" 32mmØ	Mech	10.00	pc/s	₱ 160.00	₱ 32.00	₱ 192.00	₱ 1,920.00
	2.5.1.14 Water Meter 1" (32mmØ)	ARAD	5.00	pc/s	₱ 2,445.00	₱ 489.00	₱ 2,934.00	₱ 14,670.00
	2.5.1.15 Hangers and Supports		1.00	lot	₱ 17,250.00	₱ 3,450.00	₱ 20,700.00	₱ 20,700.00
	2.5.1.16 Testing, Balancing and Adjusting		1.00	lot	₱ 57,500.00	₱ 11,500.00	₱ 69,000.00	₱ 69,000.00
	2.5.1.17 Miscellaneous and Consumables		1.00	lot	₱ 28,750.00	₱ 5,750.00	₱ 34,500.00	₱ 34,500.00
	2.5.2 Sanitary Line	Installation of Polyvinyl Chloride (PVC) pipes Series 1000, including fittings, supply and installation of hangers, supports, marking, paintings and other			₱ 0.00			
	2.5.2.1 PVC Pipe	Fujipipes S-1000 6" (150mmØ)	4.00	length/s	₱ 2,835.00	₱ 567.00	₱ 3,402.00	₱ 13,608.00
		Fujipipes S-1000 4" (100mmØ)	88.00	length/s	₱ 1,295.00	₱ 259.00	₱ 1,554.00	₱ 136,752.00
		Fujipipes S-1000 3" (75mmØ)	3.00	length/s	₱ 865.00	₱ 173.00	₱ 1,038.00	₱ 3,114.00
		Fujipipes S-1000 2" (50mmØ)	116.00	length/s	₱ 720.00	₱ 144.00	₱ 864.00	₱ 100,224.00
	2.5.2.2 PVC Wye	Fujipipes 6" (100mmØ)	7.00	pc/s	₱ 845.00	₱ 169.00	₱ 1,014.00	₱ 7,098.00
		Fujipipes 4" (100mmØ)	28.00	pc/s	₱ 70.00	₱ 14.00	₱ 84.00	₱ 2,352.00
	2.5.2.3 PVC Wye Reducer	Fujipipes 6x4" (150x100mmØ)	15.00	pc/s	₱ 670.00	₱ 134.00	₱ 804.00	₱ 12,060.00
		Fujipipes 6x3" (150x75mmØ)	3.00	pc/s	₱ 670.00	₱ 134.00	₱ 804.00	₱ 2,412.00
		Fujipipes 4x2" (100x50mmØ)	75.00	pc/s	₱ 110.00	₱ 22.00	₱ 132.00	₱ 9,900.00
		Fujipipes 3x2" (100x50mmØ)	3.00	pc/s	₱ 665.00	₱ 133.00	₱ 798.00	₱ 2,394.00
	2.5.2.4 PVC Elbow 90deg	Fujipipes 4" (100mmØ)	42.00	pc/s	₱ 135.00	₱ 27.00	₱ 162.00	₱ 6,804.00
		Fujipipes 3" (75mmØ)	6.00	pc/s	₱ 95.00	₱ 19.00	₱ 114.00	₱ 684.00
		Fujipipes 2" (50mmØ)	112.00	pc/s	₱ 80.00	₱ 16.00	₱ 96.00	₱ 10,752.00
	2.5.2.5 PVC Elbow 45deg	Fujipipes 6" (150mmØ)	22.00	pc/s	₱ 110.00	₱ 22.00	₱ 132.00	₱ 2,904.00
		Fujipipes 4" (100mmØ)	123.00	pc/s	₱ 70.00	₱ 14.00	₱ 84.00	₱ 10,332.00
		Fujipipes 3" (75mmØ)	7.00	pc/s	₱ 50.00	₱ 10.00	₱ 60.00	₱ 420.00
		Fujipipes 2" (50mmØ)	250.00	pc/s	₱ 45.00	₱ 9.00	₱ 54.00	₱ 13,500.00
	2.5.2.6 PVC Cleanout	Fujipipes 6" (150mmØ)	4.00	pc/s	₱ 115.00	₱ 23.00	₱ 138.00	₱ 552.00
		Fujipipes 4" (100mmØ)	6.00	pc/s	₱ 95.00	₱ 19.00	₱ 114.00	₱ 684.00
		Fujipipes 2" (50mmØ)	2.00	pc/s	₱ 65.00	₱ 13.00	₱ 78.00	₱ 156.00
	2.5.2.7 PVC P-trap	Fujipipes 2" (50mmØ)	31.00	pc/s	₱ 395.00	₱ 79.00	₱ 474.00	₱ 14,694.00
	2.5.2.8 PVC Tee Equal	Fujipipes 2" (50mmØ)	150.00	pc/s	₱ 140.00	₱ 28.00	₱ 168.00	₱ 25,200.00
	2.5.2.9 PVC Tee Reducer	Fujipipes 3"x2" Ø	2.00	pc/s	₱ 110.00	₱ 22.00	₱ 132.00	₱ 264.00
		Fujipipes 4"x2" Ø	4.00	pc/s	₱ 135.00	₱ 27.00	₱ 162.00	₱ 648.00
	2.5.2.10 Pipe Sleeving/Coring		1.00	lot	₱ 28,750.00	₱ 5,750.00	₱ 34,500.00	₱ 34,500.00
	2.5.2.11 Hangers and Supports		1.00	lot	₱ 17,250.00	₱ 3,450.00	₱ 20,700.00	₱ 20,700.00
	2.5.2.12 Testing, Balancing and Adjusting		1.00	lot	₱ 57,500.00	₱ 11,500.00	₱ 69,000.00	₱ 69,000.00
	2.5.2.13 Miscellaneous and Consumables		1.00	lot	₱ 28,750.00	₱ 5,750.00	₱ 34,500.00	₱ 34,500.00

	2.5.3 Plumbing Fixtures and Equipment	Installation of Plumbing Fixtures, including fittings, supply and installation of hangers, supports, marking, paintings and other			P 0.00			
	2.5.3.1 Water Closet (Tank Type)	HCG	22.00	set/s	P 30,140.00	P 6,028.00	P 36,168.00	P 795,696.00
	2.5.3.2 Lavatory (wall hung square)	HCG	20.00	set/s	P 12,220.00	P 2,444.00	P 14,664.00	P 293,280.00
	2.5.3.3 Lavatory Faucet	HCG	20.00	set/s	P 5,665.00	P 1,133.00	P 6,798.00	P 135,960.00
	2.5.3.4 Urinal	HCG	3.00	set/s	P 5,965.00	P 1,193.00	P 7,158.00	P 21,474.00
	2.5.3.5 Floor Drain 2" diameter	JAMAN	32.00	pcs	P 215.00	P 43.00	P 258.00	P 8,256.00
	2.5.3.6 Floor Cleanout 4" diameter	JAMAN	16.00	pcs	P 3,270.00	P 654.00	P 3,924.00	P 62,784.00
	2.5.3.7 Hose Bib	Kitz	1.00	set/s	P 645.00	P 129.00	P 774.00	P 774.00
	2.5.3.8 Bidet Spray	HCG	22.00	set/s	P 3,090.00	P 618.00	P 3,708.00	P 81,576.00
	2.5.3.9 Way Angle Valve	HCG	22.00	pcs	P 1,795.00	P 359.00	P 2,154.00	P 47,388.00
	2.5.3.10 Hangers, Brackets and Supports		1.00	lot	P 17,250.00	P 3,450.00	P 20,700.00	P 20,700.00
	2.5.3.11 Testing, Balancing and Adjusting		1.00	lot	P 57,500.00		P 57,500.00	P 57,500.00
	2.5.3.12 Miscellaneous and Consumables		1.00	lot	P 28,750.00		P 28,750.00	P 28,750.00
	2.5.3.13 Contingencies		1.00	lot	P 57,500.00		P 57,500.00	P 57,500.00
	2.5.4 Other scopes, miscellaneous and consumables used to complete the work		1.00	lot	P 28,750.00		P 28,750.00	P 28,750.00
III	PCCP AND WALKWAY DEVELOPMENT (Materials, Consumables, Labor & Equipment Cost)							
	3.1 SITE WORKS, CIVIL WORKS & STRUCTURAL WORKS							P 719,147.51
	3.1.1 Lay-out and Staking		84.47	l.m	P 0.00	P 165.00	P 165.00	P 13,937.55
	3.1.2 Rehabilitation of Existing Pebble Wash Finish At Walkway	FF02	124.17	sq.m	P 230.00	P 165.00	P 395.00	P 49,046.36
	3.1.3 Demolition of Old PCCP		28.15	cu.m	P 0.00	P 2,750.00	P 2,750.00	P 77,412.50
	3.1.4 Rehabilitation of Existing PCCP At Parking Area				P 0.00	P 0.00		
	3.1.4.1 Gravel Bedding	3/4"	18.30	cu.m	P 2,875.00	P 550.00	P 3,425.00	P 62,677.50
	3.1.4.2 Formworks	Phenolic Board 3/4"	20.00	sq.m	P 1,450.00	P 770.00	P 2,220.00	P 44,400.00
	3.1.4.3 Rebar Installation	Reinforcing Steel Bar 10mmØ (Grade 40)	1,156.16	kg	P 53.00	P 22.00	P 75.00	P 86,712.00
	3.1.4.4 Concreting Works	RMC (3000 PSI 28 days)	37.46	cu.m	P 6,325.00	P 1,650.00	P 7,975.00	P 298,711.60
	3.1.5 Consumables		1.00	lot	P 28,750.00	P 0.00	P 28,750.00	P 28,750.00
	3.1.6 Other Scopes, Miscellaneous and Consumables Need to Complete the Work		1.00	lot	P 57,500.00	P 0.00	P 57,500.00	P 57,500.00
IV	FRONTAGE DEVELOPMENT_ WAITING AREA (Materials, Consumables, Labor & Equipment Cost)							
	4.1 SITE WORKS , CIVIL WORKS & STRUCTURAL WORKS							P 429,477.60
	4.1.1 Lay-out and Staking		25.00	lm	P 0.00	P 165.00	P 165.00	P 4,125.00
	4.1.2 Excavation Works		0.78	cu.m	P 0.00	P 1,650.00	P 1,650.00	P 1,287.00
	4.1.3 Backfilling Works & Compaction for Excavated Areas		0.42	cu.m	P 1,725.00	P 880.00	P 2,605.00	P 1,083.51
	4.1.4 Gravel Bedding	3/4"	0.12	cu.m	P 2,875.00	P 550.00	P 3,425.00	P 411.00
	4.1.5 Rebar Installation				P 0.00	P 0.00		
	4.1.5.1 Reinforcing Steel Bar 10mmØ and 12mm	Grade 40	20.85	kg	P 53.91	P 22.00	P 75.91	P 1,582.63
	4.1.5.2 Reinforcing Steel Bar 16mmØ	Grade 60	80.56	kg	P 53.91	P 22.00	P 75.91	P 6,115.01
	4.1.6 Formworks	Phenolic Board 3/4"	3.96	sq.m	P 1,437.50	P 770.00	P 2,207.50	P 8,741.70
	4.1.7 Concreting Works	Pedestal and Footing	2.00	cu.m	P 6,325.00	P 1,650.00	P 7,975.00	P 15,950.00
	4.1.7.1 Non-shrinking Grout	25 kg	1.00	bag	P 1,725.00	P 770.00	P 2,495.00	P 2,495.00
	4.1.8 Fabrication & Erection of Structural Steel Columns and Beams and All Structural Steel Members With Complete Accessories				P 0.00	P 0.00		
	4.1.8.1 MS Plate 12mm Thk	200mmx200mm	3.00	pcs	P 1,322.50	P 528.00	P 1,850.50	P 5,551.50
	4.1.8.2 MS Plate 10mm Thk	250mmx250mm	4.00	pcs	P 1,380.00	P 528.00	P 1,908.00	P 7,632.00
	4.1.8.3 Anchor Bolt with Hex Nut and Washer 16mmØ x 250mm		12.00	sets	P 1,617.19	P 495.00	P 2,112.19	P 25,346.25
	4.1.8.4 Mechanical Expansion Bolt with Hex Nut and Washer 16mmØ	HILTI HST3 Wedge Anchor	16.00	sets	P 1,707.75	P 495.00	P 2,202.75	P 35,244.00
	4.1.8.5 Mechanical Expansion Bolt with Hex Nut and Washer 10mmØ	HILTI HST3 Wedge Anchor	12.00	sets	P 1,725.00	P 517.50	P 2,242.50	P 26,910.00
	4.1.8.6 BI Pipe Sched. 40 3"Ø	6m	2.00	length	P 7,060.00	P 2,118.00	P 9,178.00	P 18,356.00
	4.1.8.7 Rectangular Tube 2"x 3"x1.2mm Thk	6m	7.00	length	P 3,455.00	P 1,036.50	P 4,491.50	P 31,440.50
	4.1.8.8 Rectangular Tube 2"x 4"x2mm Thk	6m	7.00	length	P 6,735.00	P 2,020.50	P 8,755.50	P 61,288.50
	4.1.8.9 Rectangular Tube 4"x 6"x4.5mm Thk	6m	2.00	length	P 20,270.00	P 6,081.00	P 26,351.00	P 52,702.00
	4.1.8.10 Angle bar 2"x 2"x 3mm Thk	6m	1.00	length	P 3,720.00	P 1,116.00	P 4,836.00	P 4,836.00
	4.1.8.11 Tek screw for Metal Roofing 45mm	100 pcs	1.00	box	P 575.00	P 172.50	P 747.50	P 747.50
	4.1.8.12 Welding Rods E6013	5/64" Ø	9.00	kg	P 225.00	P 67.50	P 292.50	P 2,632.50
	4.1.9 Consumables		1.00	lot	P 57,500.00		P 57,500.00	P 57,500.00
	4.1.10 Other Civil/Structural Related Works		1.00	lot	P 57,500.00		P 57,500.00	P 57,500.00

4.2	ARCHITECTURAL WORKS							₱ 242,998.90
	4.2.1 Masonry Works							
	4.2.1.1 4" CHB plastered both sides with complete accessories to complete the works	Plant Box	8.60	sq.m	₱ 1,325.00	₱ 605.00	₱ 1,930.00	₱ 16,598.00
	4.2.1.2 Stone Cladding and Heavy Duty Adhesive	Quick Fit Cape Ebony and Fortress 25kg	7.64	sq.m	₱ 3,600.00	₱ 1,100.00	₱ 4,700.00	₱ 35,908.00
	4.2.2 Long Span, Rib-Type 0.4mm Thk. Roof Sheeting and other bended Materials to Complete the Works	Rib Type GI Sheet 0.5mm Thk (Pre-painted, Royal Blue)	15.51	sq.m	₱ 1,900.00	₱ 550.00	₱ 2,450.00	₱ 37,999.50
	4.2.3 Painting Works				₱ 0.00	₱ 0.00		
	4.2.3.1 Masonry Wall (Repaint)	Putty, Top Coat (Two Coats), Paint Thinner	114.46	sq.m	₱ 460.00	₱ 330.00	₱ 790.00	₱ 90,423.40
	4.2.3.2 Structural Steel	Primer, Paint, and Paint Thinner	34.00	sq.m	₱ 650.00	₱ 330.00	₱ 980.00	₱ 33,320.00
	4.2.4 Consumables		1.00	lot	₱ 28,750.00	₱ 0.00	₱ 28,750.00	₱ 28,750.00
TOTAL MATERIAL COST								: ₱17,754,545.95
TOTAL LABOR COST								: ₱8,851,081.28
DIRECT COST								: ₱26,605,627.22
TOTAL CONSTRUCTION COST (VAT-EX)								₱26,605,627.22
TOTAL CONSTRUCTION COST (VAT-IN)								₱29,798,302.49

Note: In order to achieve a competitive bid price, please refer to Scope Delineation in the Scope of Work sheet in order to align appropriate costing of each item in the bid bulletin in relation to the stated scope delineation

Bidder's Name : MRK CONSTRUCTION SERVICES

Bidder's Representative : ENGR. MARK RALPHAEL TIVE

Signature : 

Position :

Date :