



MRK CONSTRUCTION

DESIGN & BUILD

Subject: CSA COST PROPOSAL

Project: UBIQUITY AYALA MALL BACOLOD OFFICE FIT OUT

Location 4F Ayala Malls Capital Central Gatuslao Street Bacolod City

ITEM	DESCRIPTION	UOM	QTY	UNIT RATE	AMOUNT (PHP)
1	PRELIMINARIES				
1.01	Mobilization/ Demobilization	sum	1	1,000,000.00	1,000,000.00
1.02	Insurances (CARI and all other required policy)	sum	1	500,000.00	500,000.00
1.03	Performance and Surety Bonds	sum	1	500,000.00	500,000.00
1.04	Cleaning, clearing & hauling of construction debris, rubbish & the like	sum	1	550,000.00	550,000.00
1.05	Handling, Hauling and Lifting of Deliveries	sum	1	750,000.00	750,000.00
1.06	Professional Cleaners (Post Construction)	sum	1	550,000.00	550,000.00
1.07	Attendance to site and coordination (Management & Supervision)	sum	1	5,500,000.00	5,500,000.00
1.08	Site setting out works and markings	sum	1	450,000.00	450,000.00
1.09	Temporary facilities	sum	1	500,000.00	500,000.00
1.10	Temporary utilities	sum	1	500,000.00	500,000.00
1.11	Workers permits	sum	1	400,000.00	400,000.00
1.12	Site security (24hrs, 1 guard per shift)	sum	1	475,000.00	475,000.00
1.13	Safety Officer (2 shifts, 1 safety per shift)	sum	1	480,000.00	480,000.00
1.14	Fit-Out Deposits / Construction Bond Premium	sum	1	-	by client
1.15	Evaluation and Monitoring Fee / Review of Plans by Bldg Admin	sum	1	-	by client
1.16	Personal Protective Equipment (PPE)	sum	1	850,000.00	850,000.00
1.17	Submission & approvals of documents (Building Permit / Occupancy Permit & all other permits as required) including contractor tax for LGU permit	sum	1	400,000.00	400,000.00
1.18	Permit Plans (by Goudie) and As-Built Drawings (by GC)	sum	1	450,000.00	450,000.00
1.19	COVID Provision Cost / Hopistal Partnership	sum	1	500,000.00	500,000.00
1.20	Protection to Finishes	sum	1	400,000.00	400,000.00
1.21	Pest Control	sum	1	300,000.00	300,000.00
1.22	Other items (specify)		1	-	-
				-	
	Sub Total				15,055,000.00
				-	
2.0	Floor Finishes			-	
2.01	CP-01 ; Supply and Installation of Carpet at General Area, Color: LIGHTNING GREY, Collection: Staggered Planks; 250mm x 1000mm	m ²	3,232.30	1,400.00	4,525,220.00
2.02	TL-01 ; Supply and Installation of Tiles at Reception and Cafeteria Area, Color: GIP03 BEOLA GREY, 600mm x 600mm	m ²	886.51	1,100.00	975,161.00
2.03	TL-02 ; Supply and Installation of Accent Tiles at Reception Area, Color: GTE06 BORROMI, 600mm x 600mm	m ²	103.00	1,100.00	113,300.00
2.04	TL-03 ; Supply and Installation of Floor Planks at Coffee Points and Cafeteria and other Enclosed Room, Color: TIMBER BEIGE AS TIMBER COLLECTION LOVE TILES, 200mm x 1000mm	m ²	929.51	1,100.00	1,022,461.00
2.05	TL-06 ; Supply and Installation of Floor Tiles at Toilet, 300mm x 300mm	m ²	22.00	1,100.00	24,200.00
2.06	VL-01 ; Supply and Installation of Cement Vinyl Floor Finish, Color: PJD06 GRAY, 600mm x 600mm	m ²	56.80	1,100.00	62,480.00
2.07	Supply and Installation of 6mm x 12mm Stainless Steel Inserts	lm	30.00	2,500.00	75,000.00
2.08	Floor Screeding / Floor Levelling; if required	m ²	5,184.12	400.00	2,073,648.00
2.09	Concrete floor topping; if required	m ²	5,184.12	400.00	2,073,648.00
2.10	3-ply membrane cold applied waterproofing including top screed and concrete kerb; to pantry and sink area; if required	m ²	229.00	1,100.00	251,900.00
2.11	Hot applied waterproofing including top screed and concrete kerb; to toilet; if required	m ²	135.00	800.00	108,000.00
2.12	Zocallo / Concrete Kerb for Pantry Cabinets	lm	36.00	800.00	28,800.00
2.13	Other items (specify)			-	-
				-	
	Sub Total				11,333,818.00
				-	
3.0	Partitioning			-	
	<i>Supply and installation of partition including metal studs, channels, hangers, supports, trimmings, screws, hardwares, use of plant, paintwork, tools, equipment, and all necessary sundry items and fixing accessories to complete the works as required by the specifications.</i>			-	
3.01	P-01 Double layer drywall partition from top of Isab finish to underside of slab soffit with standard insulation (STC53 NIC50)	m ²	4,065.57	1,400.00	5,691,798.00

3.02	P-02 Single layer drywall partition from top of floor slab finish to underside of slab soffit with standard insulation (STC38 NIC35)	m²	3,668.64	1,100.00	4,035,504.00
3.03	P-03 Single layer drywall cladding / wall lining (FFL to 150mm above CFL) (STC54 NIC51)	m²	2,675.58	950.00	2,541,801.00
3.04	P-04 Single layer moisture resistant gypsum board on pantry side and double layer ordinary gypsum on office side (STC55 NIC52)	m²	697.62	1,500.00	1,046,430.00
3.05	P-05 100mm thk concrete hollow blocks partition from top of floor slab finish to underside of suspended ceiling (STC51 NIC48)	m²	327.00	850.00	277,950.00
3.06	P-06 Framed glass partition - single glazed propriety with horizontal transom (STC33 NIC30)	m²	771.43	5,000.00	3,857,150.00
3.07	P-07 Transaction Window	m²	6.00	5,000.00	30,000.00
3.08	P-08	m²	7.20	5,000.00	36,000.00
3.09	Structural support for partitions with hanging TV	set/s	20.00	4,500.00	90,000.00
3.10	Other items			-	-
				-	
	Sub Total				17,606,633.00
				-	
4.0	Wall Finishes			-	
4.01	PT-01 ; White Wall Paint Finish, General Wall Paint	m²	2,845.92	700.00	1,992,144.00
4.02	PT-03 ; Satin Finish Wall Paint, Lactation Area	m²	340.41	700.00	238,287.00
4.03	PT-04 ; Moth Mist Satin Finish; Enclosed Offices	m²	2,753.13	700.00	1,927,191.00
4.04	PT-05 ; to Match AP-01 (muted tone); Command Center	m²	353.01	700.00	247,107.00
4.05	PT-06 ; Charcoal Paint; Cafeteria Area	m²	66.00	700.00	46,200.00
4.06	SF-01 ; Bendable Fluted Finish At Reception Backwall	m²	100.80	700.00	70,560.00
4.07	SF-02 ; Cement Wall Finish	m²	7,480.26	700.00	5,236,183.26
4.08	SF-03 ; Fluted Finish, Cafeteria Room	m²	1,484.70	700.00	1,039,290.00
4.09	SF-04 ; Accent Cement Finish	m²	99.78	700.00	69,846.00
4.10	AP-01 ; Acoustic Wall Panel at Support Office	m²	169.50	700.00	118,650.00
4.11	AP-02 ; Acoustic Wall Panel at Conference Room	m²	1,071.36	700.00	749,952.00
4.12	AP-05 ; Acoustic Wall Panel at Enclosed Offices	m²	388.32	700.00	271,824.00
4.13	AP-06 ; Acoustic Wall Panel at Training Room	m²	129.81	700.00	90,867.00
4.14	AP-07 ; Acoustic Wall Panel at Lactation Room	m²	899.40	700.00	629,580.00
4.15	TL-04 ; Casa Blanca Orange Gloss backsplash at Coffee Points and Cefeteria	m²	192.42	1,500.00	288,630.00
4.16	TL-05 ; AMW- 21801 M / White Matte backsplash at Existing Toilet	m²	63.00	700.00	44,100.00
4.17	TL-07 ; Wall Tile to New Toilet	m²	187.20	1,200.00	224,640.00
4.18	Greenwall Deisgn	m²	47.28	2,500.00	118,200.00
4.19	Full Height Graphics Wall	m²	274.98	1,500.00	412,470.00
4.20	GL-01 ; Glass White Board, BRILLIANT WHITEGRAPHICOTE GLASS COATING	lm	200.00	1,500.00	300,000.00
4.21	VL-02 ; Vinyl Baseboard, TH93	lm	3,616.40	450.00	1,627,380.00
4.22	Other items			-	-
				-	
	Sub Total				15,743,101.26
				-	
5.0	Ceiling Works			-	
5.01	Perforated Acoustic Ceiling Board 600mm x 1200mm	m²	2,214.89	1,600.00	3,543,829.92
5.02	Ord Gypsum Ceiling Board with accesible manhole	m²	1,794.36	1,200.00	2,153,232.00
5.03	MR Gypsum Ceiling Board with accesible manhole	m²	917.00	1,200.00	1,100,400.00
5.04	Drop Ceiling 200mmH with Paint Finish	lm	895.00	500.00	447,500.00
5.05	Drop Ceiling between open ceiling and gypsum ceiling board (verify height) with Paint Finish	lm	830.00	500.00	415,000.00
5.06	Bulkhead in Paint Finish	lm	260.60	500.00	130,300.00
5.07	Paint finish on Slab for Open Ceiling and Gypsum Ceiling ;and exposed engineering conduits	m²	485.00	850.00	412,250.00
5.08	Decorative Hanging Ceiling Cove at Reception Area	lm	150.00	1,800.00	270,000.00
5.09	Laminated Ceiling Wood Slats at Hallway	m²	111.50	2,500.00	278,750.00
5.10	Laminated Ceiling at Conference Room	m²	85.95	2,500.00	214,875.00
5.11	Fabricated Hanging Wiremesh Décor at Cefeteria	m²	102.18	2,500.00	255,450.00
5.12	Fabricated Hanging Wiremesh with Plants Décor at Cefeteria	m²	40.80	2,500.00	102,000.00
5.13	Covelights / Grooves for finishes	lm	145.00	2,500.00	362,500.00
5.14	Other items			-	-
				-	
	Sub Total				9,686,086.92
				-	
6.0	Doors, Windows & Hardware			-	
6.01	Door - 01 ; Double Leaf Glass Pivot Door (with top and bottom rail) complete with door hardwares and accessories as per door schedule	set	2.00	150,000.00	300,000.00
6.02	Door - 02 ; Double Leaf Aluminum Framed Glass Door complete with complete with door hardwares and accessories as per door schedule	set	14.00	95,000.00	1,330,000.00
6.03	Door - 03 ; Single Leaf Aluminum Framed Glass Door complete with complete with door hardwares and accessories as per door schedule	set	66.00	55,000.00	3,630,000.00
6.04	Door - 04 ; Single Leaf Flush Hollow Core Door with vision panel (moisture resistant) complete with door hardwares and accessories	set	6.00	14,000.00	84,000.00
6.05	Door - 05 ; Single Leaf 2-HR Fire Rated Metal Door with vision panel complete with door hardwares and accessories	set	9.00	50,000.00	450,000.00

6.06	Door - 06 ; Single Leaf Flush Hollow Core Door (moisture resistant) complete with door hardware and accessories	set	7.00	14,000.00	98,000.00
6.07	Door - 07 ; Single Leaf 2-HR Fire Rated Metal Door with vision panel and kickplate complete with door hardware and accessories	set	2.00	60,000.00	120,000.00
6.08	Door - 08 ; Single Leaf Solid Core Door complete with door hardware and accessories	set	6.00	30,000.00	180,000.00
6.10	Masterkeying	lot	2.00	70,000.00	140,000.00
6.11	To repaint and make good all existing doors (e.g. Fire Exit doors, Toilet Doors, EE Room)	lot	2.00	140,000.00	280,000.00
6.12	Other items			-	-
				-	
	Sub Total				6,612,000.00
				-	
7.0	Window Finishes			-	
7.01	Supply and installation of roller blinds; chain type; typical to perimeter window (sunscreens type or Landlord approved materials; see specification)	sq.ft	900	750.00	675,000.00
7.02	New Pelmet / Curtain Cove	lm	700	1,500.00	1,050,000.00
7.03	Other items			-	-
				-	
	Sub Total				1,725,000.00
				-	
8.0	Joinery, Cabinetry & Fittings			-	
8.01	J01 ; Reception Counter (<i>see joinery details</i>)	nos	2	125,000.00	250,000.00
8.02	J02 ; Table Ledge (<i>see joinery details</i>)	nos	1	50,000.00	50,000.00
8.03	J03 ; Open Locker (<i>see joinery details</i>)	nos	1	175,000.00	175,000.00
8.04	J04 ; Base Cabinet at Toilet (<i>see joinery details</i>)	nos	1	50,000.00	50,000.00
8.05	J05 ; Full Height Cabinet with Trashbin (<i>see joinery details</i>)	nos	1	125,000.00	125,000.00
8.06	J06 ; Lactation cabinet (overhead ledge and base cabinet) (<i>see joinery details</i>)	nos	2	60,000.00	120,000.00
8.07	J07 ; Full Height Storage Cabinet (<i>see joinery details</i>)	nos	2	125,000.00	250,000.00
8.08	J08 ; Printer Cabinet (base and overhead cabinet) (<i>see joinery details</i>)	nos	2	50,000.00	100,000.00
8.09	J09 ; TV Console and TV backing (<i>see joinery details</i>)	nos	2	50,000.00	100,000.00
8.10	J10 ; Stage (<i>see joinery details</i>)	nos	1	100,000.00	100,000.00
8.11	J11 ; Full Height Storage Cabinet (<i>see joinery details</i>)	nos	1	125,000.00	125,000.00
8.12	J12 ; Hydration Point Cabinet (overhead ledge, base cabinet for trashbin and Full height cabinet for water dispenser location) (<i>see joinery details</i>)	nos	1	115,000.00	115,000.00
8.13	J13 ; Banquette Seating (<i>see joinery details</i>)	nos	2	115,000.00	230,000.00
8.14	J14 ; Bar Counter (<i>see joinery details</i>)	nos	2	125,000.00	250,000.00
8.15	J15 ; Pantry Cabinet (overhead and base cabinet) (<i>see joinery details</i>)	nos	2	75,000.00	150,000.00
8.16	J16 ; Janitor Full Height Cabinet (<i>see joinery details</i>)	nos	1	125,000.00	125,000.00
8.17	J17 ; Pass Thru Dirty Dish Cabinet (<i>see joinery details</i>)	nos	2	75,000.00	150,000.00
8.18	J18 ; Concessionaire (<i>see joinery details</i>)	nos	2	75,000.00	150,000.00
8.19	J19 ; Pantry Cabinet (overhead and base cabinet) (<i>see joinery details</i>)	nos	2	75,000.00	150,000.00
8.20	J20 ; Washing Cabinet (overhead and base cabinet) (<i>see joinery details</i>)	nos	2	50,000.00	100,000.00
8.21	J21 ; Display Cabinet (<i>see joinery details</i>)	nos	1	75,000.00	75,000.00
8.22	J22 ; Coffee Point Cabinet (overhead and base cabinet) (<i>see joinery details</i>)	nos	2	75,000.00	150,000.00
8.23	J23 ; Banquette Seating (<i>see joinery details</i>)	nos	2	100,000.00	200,000.00
8.24	J24 ; Credenza (<i>see joinery details</i>)	nos	2	50,000.00	100,000.00
8.25	J25 ; Storage Cabinet (<i>see joinery details</i>)	nos	1	125,000.00	125,000.00
8.26	J26 ; Open Shelves (<i>see joinery details</i>)	nos	1	60,000.00	60,000.00
8.27	J27 ; Overhead Ledge (<i>see joinery details</i>)	nos	1	125,000.00	125,000.00
8.28	J28 ; Full Height Cabinet (<i>see joinery details</i>)	nos	2	125,000.00	250,000.00
8.29	J29 ; Full Height Cabinet (<i>see joinery details</i>)	nos	1	125,000.00	125,000.00
8.30	J30 ; Command Center Stage (<i>see joinery details</i>)	nos	2	95,000.00	190,000.00
8.31	J32Full Height Cabinet HR (<i>see joinery details</i>)	nos	1	95,000.00	95,000.00
8.32	#REF!	nos	2	75,000.00	150,000.00
				-	
	Sub Total				4,510,000.00
				-	
9.0	Signage			-	
9.01	Supply and installation of Main signage at Reception Backwall	set	2	45,000.00	90,000.00
9.02	Supply and installation of "HEART" cut-out letters along hallway	set	2	70,000.00	140,000.00
9.03	Supply and installation of "HEAD" cut-out letters along hallway	set	2	75,000.00	150,000.00
9.04	Supply and installation of LOGO at Greenwall	set	2	140,000.00	280,000.00
9.05	Supply and installation of Gamepad at Game Room	set	1	70,000.00	70,000.00
9.06	Supply and installation of LOGO at Game Area	set	1	70,000.00	70,000.00
9.07	Supply and installation of Fire extinguisher signage	lot	1	150,000.00	150,000.00
9.08	Supply and installation of Evacuation signage	lot	1	100,000.00	100,000.00
9.09	Supply and installation of Push and pull	lot	1	150,000.00	150,000.00
9.10	Supply and installation of Room Signage	lot	1	150,000.00	150,000.00
9.11	Supply and installation of "HUSTLE" cut-out letters	set	1	70,000.00	70,000.00
9.12	Supply and installation of "BCD" cut-out letters Cafeteria	set	1	42,500.00	42,500.00
9.13	Supply and installation of "U" cut-out letters Cafeteria	set	1	22,500.00	22,500.00
9.14	Supply and installation of "O" cut-out letters Cafeteria	set	1	22,500.00	22,500.00

9.15	Other items			-	-
				-	
	Sub Total				1,507,500.00
				-	
10.0	Pantry Fixtures & Accessories			-	
10.01	SW-101 Single Tub Sink (406mm x 406mm) (see specs sheet)	nos	7	5,200.00	36,400.00
10.02	SW-102 Double Tub Sink (450mm x 785mm) (see specs sheet)	nos	7	11,500.00	80,500.00
10.03	SW-103 Water Closet (see specs sheet)	nos	24	11,500.00	276,000.00
10.04	SW-104 Wall Hung Lavatory (see specs sheet)	nos	16	2,330.00	37,280.00
10.05	SW-201 Pantry Sink Faucet (see specs sheet)	nos	4	5,100.00	20,400.00
10.06	SW-202 Pantry Gooseneck Sink Faucet (see specs sheet)	nos	10	3,500.00	35,000.00
10.07	SW-203 Lavatory Faucet (see specs sheet)	nos	24	4,200.00	100,800.00
10.08	SW-301 Toilet Trashbin (see specs sheet)	nos	35	1,150.00	40,250.00
10.09	SW-302 Waste Bin (see specs sheet)	nos	17	3,050.00	51,850.00
10.10	SW -303 Automatic Liquid Dispenser (see specs sheet)	nos	17	3,250.00	55,250.00
10.11	Other items			-	-
				-	
	Sub Total		2,467.00	-	733,730.00
				-	
11.0	Lighting Fixture			-	
11.01	LX-101 Black Suspended Lighting at Open Ceiling (see specs sheet)	nos	21	1,215.00	25,515.00
11.02	LX-102 Troffer Lights with Diffuser (see specs sheet)	lm	481	7,240.00	3,482,440.00
11.03	LX-103 Track Lighting (see specs sheet)	nos	3	14,600.00	43,800.00
11.04	LX-104 Linear Light (see specs sheet)	nos	424	1,750.00	742,000.00
11.05	LX-105 Strip Lights (see specs sheet)	lm	400	585.00	234,000.00
11.06	LX-106 Recessed Downlight (see specs sheet)	nos	1104	1,450.00	1,600,800.00
11.07	LX-201 Pendant Light at Lounge Reception Area (see specs sheet)	nos	7	17,500.00	122,500.00
11.08	LX-202 Pendant Light at Reception Area (see specs sheet)	nos	5	17,500.00	87,500.00
11.09	LX-203 Pendant Light at Coffee Point (see specs sheet)	nos	9	17,500.00	157,500.00
11.10	LX-204 Pendant Light at Game Area (see specs sheet)	nos	9	17,500.00	157,500.00
11.11	LX-204 Pendant Light at Bar counter (see specs sheet)	nos	4	17,500.00	70,000.00
11.12	#REF!	nos	5	17,500.00	87,500.00
				-	
	Sub Total		2,979.00	-	6,811,055.00
				-	
12.0	Seating and System Furniture			-	
12.01	SY-101 General Task Chair (see specs sheet)	nos	856	20,300.00	17,376,800.00
12.02	SY-102 Support Task Chair (see specs sheet)	nos	62	11,680.00	724,160.00
12.03	SY-103 O&M Chair (see specs sheet)	nos	17	10,650.00	181,050.00
12.04	SY-104 Meeting Room Chair (see specs sheet)	nos	30	28,500.00	855,000.00
12.05	SY-105 Coaching Room Chair (see specs sheet)	nos	24	37,500.00	900,000.00
12.06	SY-106 Huddle Chair (see specs sheet)	nos	12	37,550.00	450,600.00
12.07	SY-107 Manager's Chair (see specs sheet)	nos	4	42,000.00	168,000.00
12.08	SY-108 Training Room Chair (see specs sheet)	nos	50	10,650.00	532,500.00
12.09	SY-109 Conference Room Chair (see specs sheet)	nos	32	53,000.00	1,696,000.00
12.10	SY-110 Manager's Guest Room Chair (see specs sheet)	nos	7	10,650.00	74,550.00
12.11	SY-111 O&M Room Guest Chair (see specs sheet)	nos	15	9,500.00	142,500.00
12.12	SY-201 General Workstation Table (see specs sheet)	nos	853	25,700.00	21,922,100.00
12.13	SY-202 Support Workstation Table (see specs sheet)	nos	62	33,600.00	2,083,200.00
12.14	SY-202 Meeting Room Table at 4 Pax Meeting Room (see specs sheet)	nos	2	39,250.00	78,500.00
12.15	SY-203 O&M Table (see specs sheet)	nos	22	24,750.00	544,500.00
12.16	SY-204 Meeting Room Table (see specs sheet)	nos	4	39,250.00	157,000.00
12.17	SY-205 Coaching Table (see specs sheet)	nos	12	25,700.00	308,400.00
12.18	SY-206 Huddle Table (see specs sheet)	nos	10	25,700.00	257,000.00
12.19	SY-207 Manager's Table (see specs sheet)	nos	4	60,700.00	242,800.00
12.20	SY-208 Training Table (see specs sheet)	nos	26	21,000.00	546,000.00
12.21	SY-209 Conference Table (see specs sheet)	nos	2	11,600.00	23,200.00
12.22	SY-210 Conference Table (see specs sheet)	nos	1	1,100.00	1,100.00
12.23	SY-301 Phone 10 Layer Locker (see specs sheet)	nos	450	1,550.00	697,500.00
12.24	SY-302 Open Baggage 5 Layer Locker (see specs sheet)	nos	393	1,550.00	609,150.00
12.25	SY-303 2 Layer Lateral File (see specs sheet)	nos	29	850.00	24,650.00
12.26	Other items			-	-
				-	
	Sub Total		334.00	-	50,596,260.00
				-	
13.0	Loose Furniture			-	
13.01	LF-101 One Seater Armchair at Reception (see specs sheet)	nos	12	27,500.00	330,000.00
13.02	LF-102 Armchair at Reception (see specs sheet)	nos	10	70,500.00	705,000.00
13.03	LF-103 3 Seater Armchair at Reception (see specs sheet)	nos	4	570,000.00	2,280,000.00
13.04	LF-104 Dining / Coffee Chair at Coffee Point (see specs sheet)	nos	6	13,250.00	79,500.00
13.05	LF-105 Lounge Chair at Huddle Room (see specs sheet)	nos	12	32,700.00	392,400.00
13.06	LF-106 Bean Bag at Huddle Rooms and Karaoke Rooms (see specs sheet)	nos	15	5,100.00	76,500.00
13.07	LF-107 2-Seater Sofa at Huddle Rooms (see specs sheet)	nos	6	88,700.00	532,200.00
13.08	LF-108 Dining Chair at Coffee Point (see specs sheet)	nos	6	3,925.00	23,550.00
13.09	LF-109 Dining Chair without armrest at Coffee Point (see specs sheet)	nos	6	3,925.00	23,550.00

13.10	LF-110 2-Seater Sofa at Coffee Point (see specs sheet)	nos	5	88,700.00	443,500.00
13.11	LF-111 Bar Chair at Pantry (see specs sheet)	nos	18	7,500.00	135,000.00
13.12	LF-112 2-Seater Sofa at Karaoke Room and Gmaing Room (see specs sheet)	nos	2	65,450.00	130,900.00
13.13	LF-113 Armchair (long back) at Lactation Room (see specs sheet)	nos	4	32,700.00	130,800.00
13.14	LF-114 Bunk Beds (see specs sheet)	nos	36	18,650.00	671,400.00
13.15	LF-115 Dining Chair at Cafeteria (see specs sheet)	nos	48	4,200.00	201,600.00
13.16	LF-116 Bench Seat at Cafeteria (see specs sheet)	nos	32	8,400.00	268,800.00
13.17	LF-117 Bar Chair at Gaming Area (see specs sheet)	nos	12	24,500.00	294,000.00
13.18	LF-118 Massage Chair at Massage Room (see specs sheet)	nos	3	140,000.00	420,000.00
13.19	LF-119 Dining Chair at Cafeteria (see specs sheet)	nos	24	4,200.00	100,800.00
13.19	LF-201 Standard Round Table (1200mm dia) at Reception Area (see specs sheet)	nos	7	21,500.00	150,500.00
13.20	LF-202 Round Table (800mm dia) at Reception Area (see specs sheet)	nos	6	13,450.00	80,700.00
13.20	LF-203 Dining Table (700mm dia) at Coffee Point (see specs sheet)	nos	1	19,600.00	19,600.00
13.21	LF-204 Center Table at Huddle Room (see specs sheet)	nos	6	19,600.00	117,600.00
13.22	LF-205 Dining Table (800mm dia) at Coffee Point (see specs sheet)	nos	1	6,000.00	6,000.00
13.23	LF-206 Coffee Table (600mm dia) at Coffee Point (see specs sheet)	nos	1	7,850.00	7,850.00
13.24	LF-207 Center Table (800mm dia) at Karaoke Room (see specs sheet)	nos	1	20,550.00	20,550.00
13.25	LF-208 Side Table (500mm dia) at Huddle Room and Gaming Room (see specs sheet)	nos	2	13,450.00	26,900.00
13.26	LF-209 Side Table (500mm dia) at Lactation Room (see specs sheet)	nos	4	13,450.00	53,800.00
13.27	LF-210 Side Table (500mm dia) at Lactation Room (see specs sheet)	nos	2	14,000.00	28,000.00
13.28	LF-210 Dining Table at Cafeteria (see specs sheet)	nos	12	14,000.00	168,000.00
13.29	LF-211 Dining Table at Banquette Seat (see specs sheet)	nos	12	6,150.00	73,800.00
13.30	LF-212 Bench Table at Gaming Area (see specs sheet)	nos	2	12,600.00	25,200.00
13.31	LF-213 Bench Table at Pantry (see specs sheet)	nos	8	20,000.00	160,000.00
13.32	Director Chair	nos	2	53,000.00	106,000.00
13.33	Director Guest Chair	nos	4	12,500.00	50,000.00
13.34	Director's Table	nos	2	60,000.00	120,000.00
				-	
	Sub Total				8,454,000.00
			700.00	-	
14.0	Demolition / Retrofitting Works			-	
14.01	Dismantling of existing ceiling	sq.m	125	850.00	106,250.00
14.02	Dismantling of existing flooring	sq.m	125	850.00	106,250.00
14.03	Dismantling of existing partition	sq.m	450	850.00	382,500.00
14.04	Dismantling of existing joineries and cabinetries	set	1	60,000.00	60,000.00
14.05	Dismantling of existing doors	set	5	4,500.00	22,500.00
14.06	Retrofitting	lot	1	350,000.00	350,000.00
	Sub Total				1,027,500.00
GRAND TOTAL (VAT Exclusive)					151,401,684.18

Prepared by:

Engr. Mark Raphael P. Tive
MRK - QS