

QUANTITY SURVEYING PORTFOLIO

IPI Bacolod

Proposed renovation of staff
house and frontage
development

PUROK ROADSIDE, ALIJIS
BACOLOD CITY, NEGROS OCCIDENTAL

Prepared by
Engr. Mark Raphael Tive
Quantity Surveyor / Cost Estimator



PROJECT OVERVIEW

A multi-trade renovation estimate built from measurable work packages.

This client-safe sample presents representative quantities, unit rates, trade summaries and commercial totals from the supplied BOQ. It demonstrates estimating coverage across general requirements, civil and structural work, architecture, electrical, mechanical, plumbing and external development.

VAT EXCLUSIVE PHP 26.61M Direct construction cost	VAT INCLUSIVE PHP 29.80M Total construction cost
--	---

OWNER	International Pharmaceutical Incorporated
LOCATION	Purok Roadside, Alijis, Bacolod City, Negros Occidental
PROJECT	Proposed renovation of staff house and frontage development
DURATION	150 days
ROLE	BOQ preparation, quantity surveying and cost estimating
COVERAGE	General requirements, CSA, architectural, electrical, mechanical, plumbing and external works

COST STRUCTURE

Trade package summary

Package totals are retained as stated in the supplied BOQ and reconcile to the VAT-exclusive direct construction cost.

WORK PACKAGE	AMOUNT (PHP)
General requirements	3,687,060.00
Staff house - civil / structural / metal	2,212,398.05
Staff house - architectural	9,576,126.15
Staff house - electrical	3,933,705.50
Staff house - mechanical	2,550,334.00
Staff house - plumbing	2,680,938.00
PCCP / walkway - civil / structural	719,147.51
Frontage / waiting area - civil / structural	429,477.60
Frontage / waiting area - architectural	242,998.90
TOTAL CONSTRUCTION COST - VAT EXCLUSIVE	26,605,627.22

CIVIL & ARCHITECTURAL BOQ

Representative measured works

Selected items demonstrate pricing across demolition, reinforced concrete, roofing, masonry, ceilings, flooring and finishes.

TRADE	DESCRIPTION	QTY	UNIT	RATE (PHP)	AMOUNT (PHP)
Civil	Demolition works	69.39	cu.m	1,650.00	114,497.21
Structural	Grade 40 reinforcing bars	1,100.71	kg	75.00	82,553.02
Structural	Formworks	229.79	sq.m	2,000.00	459,574.45
Structural	Concreting	15.24	cu.m	7,550.00	115,062.00
Roofing	Roofing sheet	403.65	sq.m	2,300.00	928,403.23
Masonry	150 mm CHB, finished both sides	295.52	sq.m	2,100.00	620,592.00
Ceiling	Ceiling complete with framing	701.00	sq.m	1,800.00	1,261,800.00
Flooring	600 x 600 mm floor tiles	613.27	sq.m	1,800.00	1,103,889.60
Painting	White paint finish	604.92	sq.m	790.00	477,886.80

MEPF BOQ

Electrical and mechanical services

Representative cable, conduit, device, lighting, distribution, cooling and life-safety line items.

TRADE	DESCRIPTION	QTY	UNIT	RATE (PHP)	AMOUNT (PHP)
Electrical	3.5 mm2 THHN cable	1,420	m	71.50	101,530.00
Electrical	5.5 mm2 THHN cable	2,400	m	97.50	234,000.00
Electrical	25 mm PVC conduit	450	length	305.50	137,475.00
Electrical	Convenience outlet	50	pc	988.00	49,400.00
Lighting	18W LED downlight	75	pc	1,300.00	97,500.00
Lighting	6W LED downlight	120	pc	936.00	112,320.00
Electrical	Main distribution panel	1	assy	261,625.00	261,625.00
Mechanical	2 HP split-type AC unit	15	unit	86,250.00	1,293,750.00
Mechanical	25W exhaust fan	20	unit	2,586.00	51,720.00
Fire safety	Fire extinguisher	15	unit	17,250.00	258,750.00

MEPF & EXTERNAL WORKS

Plumbing and frontage development

Selected plumbing fixtures and services, followed by measurable external rehabilitation and PCCP works.

TRADE	DESCRIPTION	QTY	UNIT	RATE (PHP)	AMOUNT (PHP)
Plumbing	40 mm PPR pipe	16	length	2,676.00	42,816.00
Plumbing	100 mm PVC sanitary pipe	88	length	1,554.00	136,752.00
Plumbing	Water closet	22	set	36,168.00	795,696.00
Plumbing	Wall-hung lavatory	20	set	14,664.00	293,280.00
External	Walkway rehabilitation	124.17	sq.m	395.00	49,046.36
External	PCCP demolition	28.15	cu.m	2,750.00	77,412.50
External	PCCP reinforcing bars	1,156.16	kg	75.00	86,712.00
External	PCCP concrete	37.46	cu.m	7,975.00	298,711.60

BASIS & QUALIFICATIONS

How to read this portfolio sample

- 01 This is a curated portfolio extract, not a tender document or an offer to perform the work.
- 02 Quantities, units, rates and extensions are selected from the supplied project BOQ.
- 03 The direct construction cost is VAT exclusive; the VAT-inclusive figure applies the tax basis stated in the source.
- 04 Rates are project- and date-specific and should not be treated as current market benchmarks.
- 05 Descriptions are shortened only where necessary for presentation; original scope intent remains identifiable.
- 06 Confidential supporting material and the complete source schedule are intentionally omitted.

ESTIMATING
CAPABILITY

Drawing review | Quantity take-off | Unit-rate pricing | BOQ compilation | Cost summaries | MEPF coordination