

FEATURED PROJECT / 2025

Legacy Commercial Building

A design-and-build commercial project in La Carlota City, presented as a portfolio case study with an illustrative floor plan and preliminary cost model.

PROJECT DATA

Client: Mr. & Mrs. Samson

Location: La Carlota City, Negros Occidental

Declared project amount: PHP 10,000,000

Year completed: 2025

Role: Design & Build - Commercial

PORTFOLIO STATUS

Photographs document the completed facade and construction progress. Plan dimensions and estimate allocations are inferred assumptions for portfolio demonstration only.



IMPORTANT: This package is not an as-built record, signed plan, permit set, tender document or construction estimate. Validate all dimensions and rates before use.

01 / PROJECT EVIDENCE

From construction progress to completed facade

The supplied photographs show the two-storey commercial frontage, balcony and railing system, facade cladding, soffit finishes, external parking apron and the steel framing used during facade construction.



Observed element	Portfolio relevance
Two-storey commercial shell	Supports area-based and trade-by-trade estimating narrative
Steel facade framing and soffit	Demonstrates coordination of structural steel, cladding and finishes
Balcony, railings and glazing	Shows measurable facade components and architectural metalwork
Parking apron and landscaping	Captures external-works scope often missed in building-only take-offs

02 / CONCEPT PLAN

Assumed commercial layout for estimating demonstration

The plan below is derived from the visible facade rhythm and an assumed 18.00 m x 12.00 m footprint. It demonstrates how Mark can convert limited project information into a transparent preliminary basis while clearly recording assumptions.



03 / PRELIMINARY ESTIMATE

Illustrative allocation of the stated PHP 10.0M project value

The following is a portfolio cost model, not a reconstruction of the contractor's actual ledger. Allocations are calibrated to the project amount shown in the supplied company-profile material and provide a transparent trade structure for discussion.

Item	Trade / cost group	Illustrative amount	Share
01	Preliminaries, mobilization and temporary works	PHP 400,000	4.0%
02	Sitework, excavation and earthworks	PHP 350,000	3.5%
03	Concrete and structural works	PHP 2,250,000	22.5%
04	Masonry, plaster and partitions	PHP 750,000	7.5%
05	Structural steel and roof framing	PHP 850,000	8.5%
06	Doors, glazing, railings and metal works	PHP 650,000	6.5%
07	Architectural finishes and facade	PHP 1,500,000	15.0%
08	Plumbing and sanitary systems	PHP 550,000	5.5%
09	Electrical and lighting systems	PHP 700,000	7.0%
10	Mechanical and fire-safety allowances	PHP 450,000	4.5%
11	External works, parking and landscaping	PHP 400,000	4.0%
12	OH&P, design coordination and risk allowance	PHP 1,150,000	11.5%
TOTAL PROJECT VALUE		PHP 10,000,000	100.0%

ASSUMED GFA	INDICATIVE COST / M2	DOCUMENT BASIS
432 m2	PHP 23,148 / m2	Photographs + stated PHP 10M value

Estimate qualifications

Amounts include broad allowances for design coordination, overhead, profit and risk. They exclude land, financing, escalation after the reference period, tenant-specific equipment and any scope not visible or stated. A live estimate requires current drawings, specifications, site data, procurement strategy and dated supplier/subcontractor quotations.