

MRT

SANITIZED PORTFOLIO SAMPLE

Quantity Take-Off & Priced BOQ

A concise demonstration of drawing-referenced measurement, transparent pricing and commercial summary preparation.

PREPARED BY

Mark Raphael Tive
Quantity Take-Off Estimator
Licensed Civil Engineer

DOCUMENT STATUS

Illustrative / Sanitized
Revision 01
September 2026

IMPORTANT: This document uses fictional drawing references and illustrative rates. It contains no client-confidential drawings, supplier quotations or current tender pricing.

01 / BASIS OF ESTIMATE

Purpose, scope and limitations

Purpose

This sanitized package demonstrates how Mark structures a review-ready estimate: source references remain attached to quantities, rates remain visible, and commercial adjustments remain explicit.

Basis item	Statement
Project type	Illustrative small commercial fit-out work package
Currency	Philippine peso (PHP)
Pricing status	Illustrative portfolio rates only; not current market quotations
Measurement basis	Net measured quantities with stated units and fictional drawing references
Commercial basis	Direct cost plus illustrative overhead, profit and VAT
Revision	Rev. 01 - issued for portfolio demonstration

Included

Concrete footings, reinforcing steel, masonry, internal plaster and floor finishes. The selection is intentionally limited so the complete calculation chain is easy to audit.

Excluded

Design responsibility, permits, demolition, temporary works, testing, escalation, contingency, specialist systems and any scope not explicitly listed. Final project exclusions must always be agreed from the issued drawing and specification set.

Estimator's note

Before a live estimate is issued, drawing revisions, project location, specifications, procurement route and required level of detail are confirmed with the client.

02 / QUANTITY TAKE-OFF

Drawing-referenced measurement

Every line item retains a unit, measured quantity and source reference. References below are fictional and included only to demonstrate traceability.

Description	Unit	Quantity	Drawing reference
Concrete - footings	m3	16.00	S-201 / F1-F8
Reinforcing steel	kg	2,200	S-401 / BBS
CHB wall - 150mm	m2	180.00	A-201-204
Internal plaster	m2	360.00	A-601 / FIN-02
Floor tiles - 600x600	m2	209.00	A-701 / FF-01

Measurement quality controls

QC checkpoint	Review action
Drawing revision	Confirm all disciplines use the current issued revision.
Measurement route	Cross-check areas and volumes using a second calculation route.
Units	Confirm each measured unit matches the BOQ pricing unit.
Scope coordination	Review architectural, structural and MEP interfaces for gaps or duplication.
Record	Keep assumptions, exclusions and clarifications with the estimate.

03 / PRICED BOQ

Transparent rates and extensions

Illustrative unit rates are applied to the measured quantities. These figures are not quotations and must not be used for procurement or tender submission.

Description	Unit	Qty	Unit rate	Amount
Concrete - footings	m3	16.00	PHP 7,850.00	PHP 125,600.00
Reinforcing steel	kg	2,200	PHP 82.00	PHP 180,400.00
CHB wall - 150mm	m2	180.00	PHP 950.00	PHP 171,000.00
Internal plaster	m2	360.00	PHP 280.00	PHP 100,800.00
Floor tiles - 600x600	m2	209.00	PHP 1,450.00	PHP 303,050.00
DIRECT COST				PHP 880,850.00

Rate-build-up principle

For live work, unit rates may be built from material, labor, equipment, waste, productivity and subcontractor inputs. Each rate is dated and tied to the applicable location and specification.

Arithmetic check

Each amount equals quantity multiplied by unit rate. The five extensions reconcile to the direct-cost subtotal of PHP 880,850.00.

04 / COST SUMMARY

Clear commercial overview

Commercial component	Amount
Direct cost	PHP 880,850.00
Overhead - 10%	PHP 88,085.00
Profit - 10%	PHP 88,085.00
Subtotal before VAT	PHP 1,057,020.00
VAT - 12%	PHP 126,842.40
ESTIMATED CONTRACT VALUE	PHP 1,183,862.40

Direct-cost composition

Direct-cost composition	Amount	Share of direct cost
Materials	PHP 646,000.00	73.34%
Labor	PHP 218,000.00	24.75%
Equipment	PHP 16,850.00	1.91%
TOTAL DIRECT COST	PHP 880,850.00	100.00%

Commercial qualifications

Overhead and profit percentages are illustrative and not universal rates. VAT is applied after overhead and profit in this sample. Live project pricing is subject to confirmed scope, location, specifications, supplier validity, procurement conditions and agreed exclusions.

REQUEST A PROJECT-SPECIFIC ESTIMATE

markralphael.mrk@gmail.com
WhatsApp: +63 912 706 5976

Send the current drawings, specifications, location, scope and required submission date.